

**DEPARTMENT OF THE ARMY  
Wilmington District, Corps of Engineers  
Post Office Box 1890  
Wilmington, North Carolina 28402-1890**

Action ID No. 200431320

August 13, 2004

**PUBLIC NOTICE**

**The North Carolina Department of Transportation, ATTN: Dr. Gregory J. Thorpe, Director, Project Development and Environmental Analysis Branch, 1548 Mail Service Center, Raleigh, North Carolina 27699-1548 has applied for a Department of the Army (DA) permit TO DISCHARGE DREDGED OR FILL MATERIAL INTO 6.21 ACRES OF WETLAND, 13,321 LINEAR FEET OF STREAM CHANNEL, AND 4.47 ACRES OF OPEN WATER POND IN AND ADJACENT TO THE WATERS OF FORNEY CREEK, KILLIAN CREEK, REED CREEK AND UNNAMED TRIBUTARIES TO FACILITATE THE RELOCATION OF 10.6 MILES OF NC HIGHWAY 16 FROM NC HIGHWAY 73 ON THE SOUTH TO SR 1895 (TOWER ROAD) AT EXISTING NC 16 ON THE NORTH, WEST OF DENVER, LINCOLN AND CATAWBA COUNTIES, NORTH CAROLINA (TIP NO. R-2206 B & C, STATE PROJECT NO. 8.1830501).**

The following description of the work is taken from data provided by the applicant and from observations made during an onsite visit by a representative of the Corps of Engineers. Plans submitted with the application show the proposed construction of a new, four-lane, median-divided roadway with limited access from NC Highway 73 at the terminus of R-2206 A in Lincoln County, to an intersection with existing NC 16 at SR 1895 (Tower Road) in Catawba County, a total distance of 10.6 miles. The proposed right-of-way width for the project is approximately 325 feet including a 60-foot wide median. The applicant has identified two sections of this project designated R-2206 B and R-2206 C. Section B is 4.8 miles in length and crosses Forney Creek and 12 unnamed tributaries. On-grade intersections would be constructed at SR 1380 (Optimist Club Road) and SR 1386 (St. James Church Road). A total of 3.52 acres of wetland and 6668 linear feet of stream channel would be impacted by pipe and culvert installations, channel relocation and lateral fill encroachment on Section B. Streams are mostly perennial and vary from 3 to 5 feet wide with substrates of silt, sand, gravel and cobble. Only Sites 6B and 11B have intermittent flow. Forney Creek would be spanned by dual bridges south of Optimist Club Road and would be conveyed under the same relocated road by a 110-foot long, double cell box culvert at Site 14B. A low-flow sill would be installed in the western cell of this box culvert. Impacts to tributary streams range from 299 feet at Site 7B where a 42-inch diameter pipe would be installed in a perennial stream to 1346 feet at Site 13B where a 54-inch pipe would convey the perennial stream under the proposed road. Four wetlands ranging in size from 0.10 to 3.12 acres would be crossed by Section B. These wetlands consist of headwater forest, scrub shrub and emergent marsh. The largest wetland impact (3.12 acres) would occur at Site 10B where two existing ponds measuring 3.27 acres would also be drained. Approximately 700 linear feet of the currently impounded stream channel at Site 10B would be restored utilizing natural stream channel design techniques.

Section C is 5.8 miles long and crosses Killian Creek, Reed Creek and thirteen unnamed tributaries. An interchange would be constructed at NC Highway 150 and an on-grade intersection would be constructed at SR 1895 (Tower Road) where the new roadway would merge back into existing NC Highway 16. Dual spanning bridges would be constructed over Killian Creek at two locations (north of SR 1373 and north of SR 1349) and over Reed Creek south of the Tower Road intersection. A total of 2.66 acres of wetland and 6653 linear feet of stream channel would be impacted by pipe and culvert installation, channel relocation and lateral fill encroachment. Streams are both intermittent and perennial, vary in width from 2 to 5 feet and have either a sandy substrate or a mixture of sand, gravel and cobble. Individual channel impacts range from 230 feet at Site 4C where a 24-inch diameter pipe would be installed on an intermittent channel to 1040 feet at Site 1C where a 5-foot by 5-foot, single-cell box culvert would be installed on a perennial channel. At the outlet of this culvert, 164 linear feet of channel would be relocated utilizing natural stream channel design techniques. The proposed road would impact seven wetlands ranging in size from 0.01 to 1.69 acres. Six of the wetlands consist of headwater forest. A 1.20-acre pond with a 0.10-acre fringing marsh would be filled at Site 16C.

The project as a whole would impact 6.21 acres of wetland, 2416 linear feet of intermittent stream channel, 10,905 linear feet of perennial stream channel and 4.47 acres of man-made pond. Approximately 700 linear feet of perennial channel on the B Section and 164 linear feet on the C Section would be relocated utilizing natural stream channel design. The applicant is proposing to mitigate for stream and wetland losses by utilizing the North Carolina Ecosystem Enhancement Program (EEP). Construction of the 5.4-mile long A Section of TIP R-2206 was authorized by Department of the Army permit on May 18, 2001 and is scheduled for completion in September of 2004. The Federal Highway Administration (FHWA) approved a Final Environmental Impact Statement (FEIS) for the proposed work on May 8, 1997. A Record of Decision (ROD) was signed by the FHWA on September 4, 1997. The purpose of the proposed work is to improve safety and traffic capacity of NC 16 and provide an improved transportation corridor between Charlotte and the Lake Norman area. Plans showing representative portions of the proposed work are included with this public notice. Full plans may be obtained from the applicant or viewed at the US Army Corps of Engineers, Asheville Regulatory Field Office, 151 Patton Avenue, Room 208, Asheville, North Carolina 28801-5006.

The State of North Carolina will review this public notice do determine the need for the applicant to obtain any required State authorization. No Department of the Army (DA) permit will be issued until the coordinated State viewpoint on the proposal has been received and reviewed by this agency, nor will a DA permit be issued until the North Carolina Department of Environment and Natural Resources (NCDENR) has determined the applicability of a Water Quality Certificate as required by PL 92-500.

This application is being considered pursuant to Section 404 of the Clean Water Act (33 U.S.C. 1344). Any person may request, in writing within the comment period specified in this notice, that a public hearing be held to consider this application. Requests for public hearing shall state, with particularity, the reasons for holding a public hearing.

The District Engineer has consulted the latest published version of the National Register of Historic Places for the presence or absence of registered properties, or properties listed as being eligible for inclusion therein, and this worksite is not registered property or property listed as being eligible for inclusion in the Register. Consultation of the National Register constitutes the extent of cultural resource investigations by the District Engineer, and he is otherwise unaware of the presence of such resources. Presently, unknown archeological, scientific, prehistorical, or historical data may be lost or destroyed by work under the requested permit.

The District Engineer, based on available information, is not aware that the proposed activity will affect species, or their critical habitat, designated as endangered or threatened pursuant to the Endangered Species Act of 1973.

The decision whether to issue a permit will be based on an evaluation of the probable impacts, including cumulative impacts, of the proposed activity and its intended use on the public interest. Evaluation of the probable impacts which the proposed activity may have on the public interest requires a careful weighing of all those factors which become relevant in each particular case. The benefits which reasonably may be expected to accrue from the proposal must be balanced against its reasonably foreseeable detriments. The decision whether to authorize a proposal, and if so the conditions under which it will be allowed to occur, are therefore determined by the outcome of the general balancing process. That decision should reflect the national concern for both protection and utilization of important resources. All factors which may be relevant to the proposal must be considered including the cumulative effects thereof. Among those are conservation, economics, aesthetics, general environmental concerns, wetlands, cultural values, fish and wildlife values, flood hazards and flood plain values (in accordance with Executive Order 11988), land use, navigation, shore erosion and accretion, recreation, water supply and conservation, water quality, energy needs, safety, food and fiber production, mineral needs, considerations of property ownership, and, in general, the needs and welfare of the people. For activities involving the placement of dredged or fill materials in waters of the United States, a permit will be denied if the discharge that would be authorized by such permit would not comply with the Environmental Protection Agency's 404(b)(1) guidelines. Subject to the preceding sentence and any other applicable guidelines or criteria, a permit will be granted unless the District Engineer determines that it would be contrary to the public interest.


The Corps of Engineers is soliciting comments from the public; Federal, State and local agencies and officials; Indian Tribes and other interested parties in order to consider and evaluate the impacts, including secondary and cumulative impacts, of this proposed activity. Any comments received will be considered by the Corps of Engineers to determine whether to issue, modify, condition or deny a permit for this proposal. To make this decision, comments are used to assess impacts on endangered species, historic properties, water quality, general environmental effects and the other public interest factors listed above. Comments are used in the preparation of an Environmental Assessment (EA) and/or an Environmental Impact Statement (EIS) pursuant to the National Environmental Policy Act (NEPA). Comments are also used to determine the need for a public hearing and to determine the overall public interest of the proposed activity.

Generally, the decision whether to issue this Department of the Army (DA) permit will not be made until the North Carolina Division of Water Quality (NCDWQ) issues, denies, or waives State certification required by Section 401 of the Clean Water Act. The NCDWQ considers whether or not the proposed activity will comply with Sections 301, 302, 306 and 307 of the Clean Water Act. The application and this public notice for the DA permit serves as application to the NCDWQ for certification.

Additional information regarding the Clean Water Act certification may be reviewed at the offices of the 401 Wetlands Certification Unit, North Carolina Division of Water Quality (NCDWQ), 2321 Crabtree Blvd., Raleigh, North Carolina 27604. Copies of such materials will be furnished to any person requesting copies upon payment of reproduction costs.


All persons desiring to make comments regarding the application for Clean Water Act certification should do so in writing delivered to the North Carolina Division of Water Quality Wetlands Section, 1621 Mail Service Center, Raleigh, North Carolina 27626-0621, on or before September 3, 2004, Attention: Mr. John Dorney.

Written comments pertinent to the proposed work, as outlined above, will be received in this office, Attention: Mr. Steven Lund, until 4:15 p.m., August 27, 2004, or telephone (828) 271-7980.



# LEGEND

---WLB---- WETLAND BOUNDARY



DENOTES FILL IN WETLAND

DENOTES DRAINED WETLAND

DENOTES SURFACE WATER IMPACT (NATURAL)

DENOTES SURFACE WATER IMPACT (POND)

DENOTES TEMPORARY FILL IN WETLAND

DENOTES EXCAVATION IN WETLAND

DENOTES TEMPORARY FILL IN SURFACE WATER

DENOTES MECHANIZED CLEARING

← ← FLOW DIRECTION

TB TOP OF BANK

WE EDGE OF WATER

C PROP. LIMIT OF CUT

F PROP. LIMIT OF FILL

▲ PROP. RIGHT OF WAY

— NG — NATURAL GROUND

— PL — PROPERTY LINE

— TDE — TEMP. DRAINAGE EASEMENT

— PDE — PERMANENT DRAINAGE EASEMENT

— EAB — EXIST. ENDANGERED ANIMAL BOUNDARY

— EPB — EXIST. ENDANGERED PLANT BOUNDARY

— ▽ — WATER SURFACE

LIVE STAKES

BOULDER

— COIR FIBER ROLLS

ADJACENT PROPERTY OWNER OR PARCEL NUMBER

PROPOSED BRIDGE

PROPOSED BOX CULVERT

PROPOSED PIPE CULVERT

(DASHED LINES DENOTE EXISTING STRUCTURES)

SINGLE TREE

WOODS LINE

DRAINAGE INLET

ROOTWAD

VANE


RIP RAP

RIP RAP ENERGY DISSIPATOR BASIN

N.C. DEPT. OF TRANSPORTATION  
DIVISION OF HIGHWAYS


LINCOLN COUNTY

PROJECT: 8.1830501 (R-2206B)  
NC-16 BYPASS





MATCHLINE A-A



⑨ PLAN VIEW  
SITE 10B

N.C. DEPT. OF TRANSPORTATION  
DIVISION OF HIGHWAYS

LINCOLN COUNTY

PROJECT: 8-1830501 (R-2206B)  
NC-16 BYPASS

SHEET 15 OF 35

1/16/04



DENOTES SURFACE WATER  
IMPACT (POND)



DENOTES DRAINED  
WETLANDS




CROSS VANE  
SEE DETAIL SHEET



NATURAL STREAM DESIGN —  
SEE DETAIL SHEET  
AND SUMMARY SHEET  
OF

PUBLIC NOTICE SHEET 5 OF 22

MATCHLINE B-B



## PLAN VIEW SITE 10B

N.C. DEPT. OF TRANSPORTATION  
DIVISION OF HIGHWAYS

LINCOLN COUNTY

PROJECT: 81830501 (R-2206B)  
NC-16 BYPASS

SHEET 16 OF 35  
1/16/04

DENOTES SURFACE WATER  
IMPACT (POND) P P

DENOTES DRAINED  
WETLAND D D

20  
10  
0

SHEET 17 OF 35 1/16/04

LINCOLN COUNTY

PROJECT: 81830501 (R-2206B)  
NC-16 BYPASS

N.C. DEPT. OF TRANSPORTATION  
DIVISION OF HIGHWAYS


DENOTES DRAINED  
 WETLAND


PJ SHEET 7 OF 22



PLAN VIEW  
SITE 10B

MATCHLINE C-C





**N.C. DEPT. OF TRANSPORTATION  
DIVISION OF HIGHWAYS**

## LINCOLN COUNTY

**PROJECT: 8.1830501 (R-2206B)  
NC-16 BYPASS**


SHEET 18 OF 35 1/16/04

PROFILE  
SITE 10B

#### HORIZONTAL SCALE


2

VERTICAL SCALE P1 SHEET 8 OF 22



## PLAN VIEW SITE 11B

DENOTES SURFACE WATER  
IMPACT (NATURAL)



PJ SHEET 9 OF 22


N.C. DEPT. OF TRANSPORTATION  
DIVISION OF HIGHWAYS


LINCOLN COUNTY

PROJECT: 81830501 (R-2206B)  
NC-16 BYPASS

SHEET 19 OF 35


1/16/04





PN SHEET 11 OF 22  
**PLAN VIEW**  
**SITE 14B**

DENOTES MECHANIZED  
CLEARING



DENOTES FILL IN  
WETLANDS



DENOTES SURFACE WATER  
IMPACT (NATURAL)



10      0      20

N.C. DEPT. OF TRANSPORTATION  
DIVISION OF HIGHWAYS

LINCOLN COUNTY


PROJECT: 81830501 (R-2206B)  
NC-16 BYPASS

SHEET 22 OF 35

1/16/04

-Y9- PROFILE GRADE LINE (PROPOSED)

230  
225  
220  
215  
210



2 @ 4.3m x 3.0m RCBC  
220  
215  
210

EXISTING GROUND LINE  
AT RCBC INLET  
EXISTING STREAM BED  
PROPOSED STREAM BED  
0.45m CONC. SILL  
0.45m CONC. SILL

NOTES: 0.45m CONC. SILL PROVIDED IN RIGHT  
RCBC BARREL TO RETAIN NATURAL  
LOW FLOW CHANNEL WIDTH.  
INVERTS OF CULVERT ARE SET 0.3m (1.0')  
BELOW STREAM TO ALLOW FORMATION OF  
NATURAL BED.

210  
+40 +20 19+00 +60 +40 +20 18+00 +80 +60 +40



PROFILE  
SITE 14B

N.C. DEPT. OF TRANSPORTATION  
DIVISION OF HIGHWAYS

LINCOLN COUNTY

PROJECT: 81030501 (R-2206B)  
NC-16 BYPASS

PNO SHEET 12 OF 22

SHEET 23 OF 25 1/16/04

IMPACT SUMMARY (ENGLISH)							WETLAND IMPACTS				SURFACE WATER IMPACTS			
Site No.	Station (From/To)	Structure Size	Fill In Wetlands (ac)	Temp. Fill In Wetlands (ac)	Excavation In Wetlands (ac)	Mechanized Clearing (Method III) (ac)	Fill In SW (Natural) (ac)	Fill In SW (Pond) (ac)	Fill In SW (ac)	Temp. Fill In SW (ac)	Existing Channel Impacted (ft)	Natural Stream Design (ft)		
1B	-Y12-15+81 Lt to 106+25 Rt	900mm	0.099			0.010	0.027				377.6			
2B	-L- 114+65 Lt to 115+27 Rt	900mm				0.025					429.8			
3B	-L- 121+69 Rt to 122+44 Rt	1650mm									678.5			
4B	-L- 132-03 Rt to 133+12 Lt	1 @ 2.1m x 1.5m RCBC				0.104					834.3			
6B	-L- 139-59 Rt to 140+01 Lt	1050mm				0.196					355.3			
7B	-L- 142-91 Lt to 143+36 Rt	1050mm				0.022					299.2			
8B	-L- 145-50 Rt to 145+88 Lt	1050mm				0.030					382.2			
9B	-L- 150-96 Rt to 151+55 Lt	1200mm	0.173			0.020	0.039				531.8			
10B	-L- 156-75 Rt to 157+75 Rt	1 @ 2.7m x 1.8m RCBC	3.116 [2]			3.267 [1]					459.3			
	-L- 157-94 Rt to 160+37 Lt										242.8			
11B	-L- 169-69 Lt to 170+01 Rt	1050mm				0.042					563.3			
12B	-L- 172+55 Lt to 173+39 Rt	750mm				0.052					660.7			
13B	-L- 177-58 Rt to 178+75 Lt	1350mm				0.101					1345.8			
14B	-Y9-REV 18-46 Rt to 18-56 Lt	2 @ 4.3m x 3.0m RCBC	0.084			0.020	0.059				209.3			
	PROJECT TOTALS		3.472	0.000	0.000	0.050	0.684	3.267	0.000	6667.8	702.1			

NOTES:  
 Site 5B Removed Due To No Impact  
 Denotes Draining Of Pond Impact.  
 Denotes Draining Of Wetland Impact.


N.C. DEPT. OF TRANSPORTATION  
 DIVISION OF HIGHWAYS


LINCOLN COUNTY

PROJECT: 8-1630501  
 NCDOT T.I.P. No. R-2206B

PJ SHEET 13 OF 22

SHEET 25 OF 35  
 1/16/2004





**PLAN VIEW**  
**SITE 1C**

A horizontal ruler scale with markings at 10, 15, and 20. A vertical tick mark is present at the 15 position.

DENOTES SURFACE WATER  
IMPACT (NATURAL)


**N.C. DEPT. OF TRANSPORTATION  
DIVISION OF HIGHWAYS**

**PROJECT: 34383.1.1 (R-2206C)**  
**NC-16 BYPASS**

SHEET 3 OF 35


1/16/04

MATCHLINE -L- STA.182+60



## PLAN VIEW SITE 1C

PN SHEET 16 OF 22



DENOTES SURFACE WATER  
IMPACT (NATURAL)



N.C. DEPT. OF TRANSPORTATION  
DIVISION OF HIGHWAYS


LINCOLN & CATAWBA COUNTIES


PROJECT: 34383.1.1 (R-2206C)  
NC-16 BYPASS

SHEET 4 OF 35

1/16/04

REVISED 4/29/04






## PLAN VIEW SITE 4C

DENOTES FILL IN  
WETLANDS




DENOTES SURFACE WATER  
IMPACT (NATURAL)



N.C. DEPT. OF TRANSPORTATION  
DIVISION OF HIGHWAYS

LINCOLN & CATAWBA COUNTIES

PROJECT: 34383.1.1 (R-2206C)  
NC-16 BYPASS



Site No.	Station (From/To)	Structure Size	IMPACT SUMMARY (ENGLISH)					
			WETLAND IMPACTS			SURFACE WATER IMPACTS		
Fill In Wetlands (ac)	Temp. Fill In Wetlands (ac)	Excavation In Wetlands (ac)	Mechanized Clearing (Method III) (ac)	Fill In SW (Natural) (ac)	Fill In SW (Pond) (ac)	Temp. Fill In SW (ac)	Existing Channel Impacted (ft) (ft)	Natural Stream Design (ft)
1C	-L- 181+48 Rt to 181+74 Lt	750mm		0.017		220.1		
	-L- 182+23 Rt to 182+49 Lt	1200mm	0.032			425.5		
	-L- 183+92 Lt to 183+99 Rt	1 @ 1.5m x 1.5m RCBC	0.099			1040.3		
2C	-L- 190+68 Lt to 191+05 Rt	1500mm	0.044			447.8		
	-L- 190+96 Lt to 192+03 Rt	900mm	0.025			464.9		
3C	-L- 194+96 Lt to 195+14 Lt	600mm	0.012			145.0		
4C	-L- 196+71 Lt to 197+40 Lt	600mm	0.007			230.3		
6C	-L- 202+25 Rt to 203+66 Rt	-		0.042		571.8		
7C	-L- 207+91 Rt to 207+96 Rt	750mm		0.017		230.0		
8C	-L- 208+59 Rt to 209+04 Rt	-		0.005		51.5		
9C	-L- 211+68 Lt to 211+95 Rt	1050mm		0.049		335.0		
	-L- 211+95 Rt to 212+42 Lt	750mm	0.030			203.4		
10C	-L- 217+75 Lt to 218+37 Rt	750mm	0.089	0.007	0.022	303.5		
11C	-L- 221+11 Rt to 221+37 Rt	-	0.101					
14C	-L- 262+64 Rt to 263+00 Rt	900mm	0.173					
	-L- 262+93 Rt to 264+38 Lt	1050mm	0.492			631.6		
	SHEET TOTAL	0.874	0.000	0.000	0.029	0.483	0.000	5300.7
	SHEET TOTAL	0.874	0.000	0.000	0.029	0.483	0.000	164.0

NOTE: Sites 5C, 12C and 13C Removed Due To No Impact.

N.C. DEPT. OF TRANSPORTATION  
DIVISION OF HIGHWAYS

LINCOLN / CATAWBA COUNTIES

PROJECT: 34383.11  
NC DOT T.I.P. No: R-2208C

SHEET 23 OF 35

PN SHEET 20 OF 22






**NOTES**


1. THE CONTRACTOR SHALL LAY OUT THE CHANNEL ALIGNMENT WHICH CONSISTS OF STRAIGHT LINE SECTION OF EACH RAILROAD, EXCEPT AT THE CENTER LINE OF THE CHANNEL. EACH LINE BEING THE RELATED RADUS AND SCREWBED CENTER LINE. THE TANGENT SECTION AT CONNECTING SUCCESSIVE BEVELS WITH STRAIGHT LINE, RADIUS 60'-0".
2. FIELD ADJUSTMENTS OF THE ALIGNMENT MAY BE REQUIRED TO AVOID CERTAIN OBSTACLES. APPROVAL BY THE ENGINEER OF THE STATE-OUT ALIGNMENT SHALL BE REQUIRED PRIOR TO INITIATION OF THE CONSTRUCTION OF THE CHANNEL.

3. LOCATE ROCK VAMES ACCORDING TO PLATE SHEET.
  4. NUMBER OF ROOTRODS INSTALLED TO BE DETERMINED ON SITE.
  5. ROOTRODS TO BE SPACED AS DIAMETER OF ROOT BASE.
  6. FIRST LOG ANCHOR ROCK TO BE PLACED ON THE DOWNHILL END OF EACH ROOTROD SO THAT IT LEARNS AGAINST THE LOG ON THE EAST SIDE, WAIT TILL THE CHANNEL.
  7. WHEN BACKFILLED OVER AND AROUND FOOTER LOGS, ROOTWAD LOGS AND ANCHOR ROCKS FRANT AND SECURE ALL COMPONENTS INCLUDING JOINTS, CONNECTIONS AND GAPS.
  8. PLANTERS SHOULD BE PLACED ABOVE BANKFULL DEPTH.

## MORPHOLOGICAL MEASUREMENT TABLE



### CROSS VANE ROCK WEIR DETAILS



## TYPICAL PROFILE

THE POOL TO FOLLOW SHALL BE MEASURED AS THE DISTANCE FROM THE MOUTH OF THE UPSTREAM BEND TO THE MOUTH OF THE DOWNSTREAM BEND.  
REFFER TO MORPHOLOGICAL MEASUREMENT TABLE AND PLAN SHEET FOR DIMENSIONS.

1530

5

N.C. DEPT. OF TRANSPORTATION  
DIVISION OF HIGHWAYS

## LINCOLN & CATAWBA COUNTIES

**PROJECT: 34383.1.1 (R-2206C)**  
**NC-16 BYPA<sub>CS</sub>**

NATURAL CHANNEL DESIGN TYPICALS