

DEPARTMENT OF THE ARMY
Wilmington District, Corps of Engineers
Post Office Box 1890
Wilmington, North Carolina 28402-1890

11 December 2008

NOTICE

This notice from the United States Army Corps of Engineers, Wilmington District, Operations Division, serves as notification to all interested parties of proposed upcoming maintenance dredging, subject to the availability of funds, within the Federally maintained waterways of North Carolina. As with all email attachments, be sure to check for viruses prior to opening the attachment. The current notice involves:

1. Manteo (Shallow bag) Interior Channels, Far Creek, NC

- (a) Estimated amount: Approximately 854,300 cubic yards
- (b) Contract award: 4 March 2008
- (c) Start work: 17 March 2008
- (d) Estimated complete work: 31 March 2009
- (e) Type dredge: Pipeline
- (f) Disposal: Upland, Control of Effluent
- (g) Contractor: Cottrell Dredging
- (h) Environmental Window: 1 Sept – 31 Mar (for disposal on bird islands), Far Creek dredging window is 1 Oct to 31 Mar
- (i) Contract number: W912HN-08-C-0017

2. Wilmington Harbor Anchorage Basin

- (a) Estimated amount: Approximately 1,390,000
- (b) Contract award: 28 August 2008
- (c) Start work: 23 September 2008
- (d) Estimated complete work: 31 January 2009
- (e) Type of dredge: Pipeline
- (f) Disposal: Eagle Island
- (g) Contractor: Southern Dredging Company, Inc.
- (h) Environmental Window: 1 Aug – 31 Jan
- (i) Contract number: W912HN-08-C-0051

3. Wilmington Harbor Outer Ocean Bar

- (a) Estimated amount: Approximately 750,000
- (b) Contract award: 20 November 2008
- (c) Start work: 14 December 2008
- (d) Estimated complete work: 31 March 2009
- (e) Type of dredge: Hopper
- (f) Disposal: ODMDS
- (g) Contractor: Unknown until award date
- (h) Environmental window: 1 Dec – 31 Mar
- (i) Contract number: Assigned at award of contract

4. Wilmington Harbor Inner (Ocean Bar)

- (a) Estimated amount: Approximately 850,000
- (b) Contract award: 16 December 2008
- (c) Start work: 1 January 2009
- (d) Estimated complete work: 30 April 2009
- (e) Type of dredge: Pipeline
- (f) Disposal: Caswell Beach/portions of Oak Island Beach
- (g) Contractor: Unknown until award date
- (h) Environmental window: 15 Nov – 30 Apr
- (i) Contract number: Assigned at award of contract

5. Morehead City (Inner Harbor/Ocean Bar)

- (a) Estimated amount: Approximately 550,000
- (b) Contract award: N/A
- (c) Start work: 26 January 2009
- (d) Estimated complete work: 20 February 2009
- (e) Type of dredge: Hopper
- (f) Disposal: Nearshore
- (g) Contractor: McFarland (Government-owned Plant)
- (h) Environmental window: 1 Jan – 31 Mar

6. Military Ocean Terminal – Sunny Point (MOTSU)

- (a) Estimated amount: Approximately 920,000
- (b) Contract award: 15 October 2008
- (c) Start work: 25 October 2008
- (d) Estimated complete work: 26 January 2009
- (e) Type of dredge: Bucket & Barge
- (f) Disposal: ODMDS
- (g) Contractor: Norfolk Dredging
- (h) Environmental window: N/A
- (i) Contract number: W912HN-08-C-0074

7. Atlantic Intracoastal Waterway – Maintenance Dredging (AIWW)

- (a) Estimated amount: Approximately 500,000
- (b) Contract award: 15 December 2008
- (c) Start work: 1 January 2009
- (d) Estimated complete work: 31 March 2009
- (e) Type of dredge: Pipeline
- (f) Disposal: Adjacent beaches
- (g) Contractor: Unknown until award date
- (h) Environmental window: 16 November – 30 April (sea turtles)
Sept 1 – 31 Mar (nesting birds)
- (i) Contract number: Assigned at award of contract