NOTES:

SOUNDINGS ARE EXPRESSED IN FEET AND TENTHS AND REFER TO LOCAL M.L.W..
PROJECT SURVEYED WITH DISTRICT SURVEY VESSEL "WANCHESE". USING D.G.P.S. HORIZONTAL POSITIONING EQUIPMENT AND 200 KHZ SOUNDING EQUIPMENT.

TIDE GAGE LOCATED AT: D.M. #10, 6 NAILS, M.L.W., BFT. DATUM.

HORIZONTAL DATUM NAD 1983

NAVIGATION AIDS LOCATED BY SURVEY VESSEL. ACCURACY +/- 3 METERS.

BUOY	# 1	2361709	157336
LT. BUOY	# 2	2361978	157738
BUOY	# 3	2360637	158429
BUOY	# 4	2360792	159095
LT. BUOY	# 5	2359816	159174
LT. BUOY	# 6	2359951	160099
BUOY	# 7	2358335	160072
LT. BUOY	# 8	2358288	160620
D.M.	# 10	2358895	161765
JUNCTION	WC	2357965	161588

THIS PROJECT WAS DESIGNED BY THE WILMINGTON DISTRICT OF THE U.S. ARMY CORPS OF ENGINEERS. THE INITIALS OR SIGNATURES AND REGISTRATION DESIGNATIONS OF INDIVIDUALS APPEAR ON THESE PROJECT DOCUMENTS WITHIN THE SCOPE OF THEIR EMPLOYMENT AS REQUIRED BY ER 1110-1-8152.

THE INFORMATION DEPICTED ON THIS MAP REPRESENTS THE RESULT OF SURVEYS MADE ON THE DATE INDICATED AND CAN ONLY BE CONSIDERED AS INDICATING THE GENERAL CONDITIONS EXISTING AT THAT TIME.

CONDITION SURVEY

SYMBOL	DESCRIPTIONS	DATE	APPROVED
	REVISIONS		

U.S. ARMY ENGINEER DISTRICT
CORPS OF ENGINEERS
WILMINGTON, NORTH CAROLINA

US ARMY CORPS OF ENGINEERS

WRIGHTSVILLE BEACH, NORTH CAROLINA

MASONBORO INLET

SURVEYED BY: M.K.A.	SCALE: 1" = 300'	PLATE NUMBER:	SURVEYED: 27,28 JULY 1999
DRAWN BY J.D.E.	DATE: 29 JULY 1999		
CHECKED BY	MAP FILE NO. MI 105-99-1		SHEET OF
SUBMITTED BY			
APPROVED BY			
CHIEF, NAVIGATION SEC.			

/NAV/BANK/SURVEYS/INLETS.MB/1999/MBIDB208.CD. MBI209CS.CD/MBIDB208.XST. MBI209CS.XST/.DGN

g:/inlets/mb/1999/mbidb209.dgn Aug. 01, 2001 15:02:58