

GENERAL SITE NOTES:

1. "PRIOR TO STARTING CONSTRUCTION CONTRACTOR SHALL BE RESPONSIBLE TO MAKE SURE THAT ALL REQUIRED PERMITS AND APPROVALS HAVE BEEN OBTAINED. NO CONSTRUCTION OR FABRICATION SHALL BEGIN UNTIL THE CONTRACTOR HAS RECEIVED AND THOROUGHLY REVIEWED ALL PLANS AND OTHER DOCUMENTS APPROVED BY ALL OF THE PERMITTING AUTHORITIES."

2. ALL WORK SHALL BE PERFORMED IN ACCORDANCE WITH THESE PLANS AND SPECIFICATIONS AND THE REQUIREMENTS AND STANDARDS OF THE LOCAL GOVERNING AUTHORITY.

3. THE RIGHT OF WAY INFORMATION, TOPOGRAPHY, UTILITIES, AND PHYSICAL FEATURES WERE TAKEN FROM A TOPOGRAPHIC SURVEY AND BOUNDARY PLAT CONDUCTED BY ROCHESTER & ASSOCIATES, INC. FIELD DATA WAS COLLECTED IN AUGUST OF 2024.

4. THE LOCATIONS OF UNDERGROUND FACILITIES SHOWN ON THIS PLAN ARE BASED ON FIELD SURVEYS AND LOCAL UTILITY COMPANY RECORDS. IT SHALL BE THE CONTRACTOR'S FULL RESPONSIBILITY TO CONTACT THE VARIOUS UTILITY COMPANIES TO LOCATE THEIR FACILITIES PRIOR TO STARTING CONSTRUCTION. NO ADDITIONAL COMPENSATION SHALL BE PAID TO THE CONTRACTOR FOR DAMAGE AND REPAIR TO THESE FACILITIES CAUSED BY HIS WORK FORCE.

5. ALL DIMENSIONS AND GRADES SHOWN ON THE PLANS SHALL BE FIELD VERIFIED BY THE CONTRACTOR PRIOR TO CONSTRUCTION. CONTRACTOR SHALL NOTIFY THE OWNER'S CONSTRUCTION MANAGER IF ANY DISCREPANCIES EXIST PRIOR TO PROCEEDING WITH CONSTRUCTION FOR NECESSARY PLAN OR GRADE CHANGES. NO EXTRA COMPENSATION SHALL BE PAID TO CONTRACTOR FOR WORK HAVING TO BE REDONE DUE TO DIMENSIONS OR GRADES SHOWN INCORRECTLY ON THESE PLANS IF SUCH NOTIFICATION HAS NOT BEEN GIVEN.

6. ALL DIMENSIONS ARE TO THE BACK OF CURB UNLESS OTHERWISE NOTED.

7. ANY CHANGES OR ALTERATIONS MADE TO THESE CONSTRUCTION DRAWINGS WITHOUT THE WRITTEN APPROVAL OF ROCHESTER AND ASSOCIATES, INC. VOIDS THE SEAL SHOWN HEREON AND ANY LIABILITY ASSOCIATED WITH THIS PROJECT. THE ORIGINAL DRAWINGS ARE KEPT ON FILE FOR VERIFICATION OF ANY CHANGES.

8. ALL CONSTRUCTION SHALL CONFORM TO CURRENT APPLICABLE CLAY COUNTY STANDARDS AND SPECIFICATIONS.

9. SITE IS LOCATED IN HAWASSEE TOWNSHIP, CLAY COUNTY, NORTH CAROLINA.

10. PROPOSED USE: 3 NEW DOCKS, LAKE DREDGING, 18 ATTACHED SINGLE FAMILY UNITS, AND 43 DETACHED SINGLE FAMILY UNITS.

11. DEVELOPER: BROWN HAVEN HOMES

12. CONTRACTOR SHALL NOTIFY CLAY COUNTY 24 HOURS BEFORE THE BEGINNING OF EVERY PHASE OF CONSTRUCTION.

13. UTILITY SERVICE:

GAS

WATER

COMM.

POWER

SEWER

TBD

TBD

TBD

TBD

TBD

14. 24 HOUR CONTACT: JOHN ALLEN
MOBILE: (706) 970-2456 EMAIL: JOHN@BROWNHAVENHOMES.COM

15. ENGINEERING CONTACT: MICHAEL STREAM, P.E., (770) 718-0600

16. PORTIONS OF THIS PROPERTY ARE LOCATED IN A FLOOD HAZARD ZONE "AE" AS PER F.E.M.A. INSURANCE RATE MAP OF CLAY COUNTY, NORTH CAROLINA. COMMUNITY PANEL NO. 3700548900J EFFECTIVE DATE NOVEMBER 19, 2008.

17. THERE ARE STREAMS AND WETLANDS ON OR WITHIN 200' OF THE PROJECT SITE.

18. THERE ARE NO STREAMS REQUIRING STATE OR LOCAL BUFFERS ON OR WITHIN 200' OF THE PROJECT SITE.

19. THIS SITE DOES NOT CONTAIN ANY KNOWN CEMETERIES.

20. ALL RETAINING WALLS WILL BE PERMITTED SEPARATELY.

21. ALL LIGHTING WILL BE LOW LEVEL AND NON-SPILL.

22. ALL PLANT MATERIAL CONFORMING TO AMERICAN STANDARD FOR NURSERY STOCK.

EROSION CONTROL NOTES:

1. DESCRIPTION: 3 NEW DOCKS, LAKE DREDGING, 15 ATTACHED SINGLE FAMILY UNITS, AND 44 DETACHED SINGLE FAMILY UNITS.

2. EXISTING CONDITIONS: OPEN GRASSED FIELDS & WETLANDS

3. ADJACENT AREAS: THE SITE IS BOUNDED TO THE NORTH-EAST BY NC 175 AND A CHURCH, AND ON OTHER SIDES BY SINGLE FAMILY RESIDENTIAL LOTS.

4. SOIL CLEAN UP AND CONTROL PRACTICES:

(A) LOCAL, STATE AND MANUFACTURER'S RECOMMENDED METHODS FOR SPILL CLEANUP WILL BE CLEARLY POSTED AND PROCEDURES WILL BE MADE AVAILABLE TO SITE PERSONNEL.

(B) MATERIAL AND EQUIPMENT NECESSARY FOR SPILL CLEANUP WILL BE KEPT IN THE MATERIAL STORAGE AREAS. TYPICAL MATERIAL AND EQUIPMENT INCLUDES, BUT IS NOT LIMITED TO, BROOMS, DUSTPANS, MOPS, GLOVES, GOGGLES, CAT LITTER, SAND, SAWDUST AND PROPERLY LABELED PLASTIC AND METAL WASTE CONTAINERS.

(C) SPILL PREVENTION PRACTICES AND PROCEDURES WILL BE REVIEWED AFTER A SPILL AND ADJUSTED AS NECESSARY TO FUTURE SPILLS.

(D) ALL SPILLS WILL BE CLEANED UP IMMEDIATELY UPON DISCOVERY. ALL SPILLS WILL BE REPORTED AS REQUIRED BY LOCAL, STATE AND FEDERAL REGULATIONS.

(E) FOR SPILLS THAT IMPACT SURFACE WATER (LEAVE A SHEEN ON SURFACE WATER). THE NATIONAL RESPONSE CENTER (NRC) WILL BE CONTACTED WITHIN 24 HOURS AT 1-800-426-2675.

(F) FOR SPILLS OF AN UNKNOWN AMOUNT, THE NATIONAL CENTER (NRC) WILL BE CONTACTED WITHIN 24 HOURS AT 1-800-426-2675.

(G) FOR SPILLS GREATER THAN 25 GALLONS AND NO SURFACE WATER IMPACTS, THE NORTH CAROLINA DEQ WILL BE CONTACTED WITHIN 24 HOURS.

(H) FOR SPILLS LESS THAN 25 GALLONS AND NO SURFACE WATER IMPACTS, THE SPILL WILL BE CLEANED UP AND LOCAL AGENCIES WILL BE CONTACTED AS REQUIRED.

(I) THE CONTRACTOR SHALL NOTIFY THE LICENSED PROFESSIONAL WHO PREPARED THIS PLAN IF MORE THAN 1320 GALLONS OF PETROLEUM IS STORED ONSITE (THIS INCLUDES CAPACITIES OF EQUIPMENT) OR IF ANY ONE PIECE OF EQUIPMENT HAS A CAPACITY GREATER THAN 560 GALLONS. THE CONTRACTOR WILL NEED A SPILL PREVENTION CONTAINMENT AND COUNTER MEASURES PLAN BY THAT LICENSED PROFESSIONAL.

5. INSPECTIONS & RECORD KEEPING:

a. Permittee requirements.

(1). Each day when any type of construction activity has taken place at a primary permittee's site, provided by the primary permittee, shall inspect: (a) all areas at the primary permittee's site where petroleum products are stored, used, or handled for spills and leaks from vehicles and equipment and (b) all locations at the primary permittee's site where vehicles enter or exit the site for evidence of off-site sediment tracking .. These inspections must be conducted until a Notice of Termination is submitted.

(2). Measure rainfall once every 24 hours except any non-working Saturday, non-working Sunday and non-working Federal holiday until a Notice of Termination is submitted. Measurement of rainfall may be suspended if all areas of the site have undergone final stabilization or established a crop of annual vegetation and a seeding of target perennials appropriate for the region.

(3). Certified personnel (provided by the primary permittee) shall inspect the following at least once every seven (7) calendar days and within 24 hours of the end of a storm that is 0.5 inches rainfall or greater (unless such storm ends after 5:00 PM on any Friday or on any non-working Saturday, non-working Sunday or any non-working Federal holiday in which case the inspection shall be completed by the end of the next business day and/or working day, whichever occurs first): (a) disturbed areas of the primary permittee's construction site ; (b) areas used by the primary permittee for storage of materials that are exposed to precipitation ; and (c) structural control measures. Erosion and sediment control measures identified in the Plan applicable to the primary permittee's site shall be observed to ensure that they are operating correctly. Where discharge locations or points are accessible, they shall be inspected to ascertain whether erosion control measures are effective in preventing significant impacts to receiving water(s). For areas of a site that have undergone final stabilization or established a crop of annual vegetation and a seeding of target perennials appropriate for the region, the permittee must comply with Part IV.D.4.a.(4). These inspections must be conducted until a Notice of Termination is submitted.

(4). Certified personnel (provided by the primary permittee) shall inspect at least once per month during the term of this permit (i.e., until a Notice of Termination is received by EPD) the areas of the site that have undergone final stabilization or established a crop of annual vegetation and a seeding of target perennials appropriate for the region. These areas shall be inspected for evidence of, or the potential for, pollutants entering the drainage system and the receiving water(s). Erosion and sediment control measures identified in the Plan shall be observed to ensure that they are operating correctly. Where discharge locations or points are accessible, they shall be inspected to ascertain whether erosion control measures are effective in preventing significant impacts to receiving water(s).

(5). Based on the results of each inspection, the site description and the pollution prevention and control measures identified in the Erosion, Sedimentation and Pollution Control Plan, the Plan shall be revised as appropriate not later than seven (7) calendar days following each inspection. Implementation of such changes shall be made as soon as practical but in no case later than seven (7) calendar days following each inspection.

(6). A report of each inspection that includes the name(s) of certified personnel making each inspection, the date(s) of each inspection, construction phase (i.e., initial, intermediate or final), major observations relating to the implementation of the Erosion, Sedimentation and Pollution Control Plan, and actions taken in accordance with Part IV.D.4.a.(5), of the permit shall be made and retained at the site or be readily available at a designated alternate location until the entire site or that portion of a construction project that has been phased has undergone final stabilization and a Notice of Termination is submitted to EPD. Such reports shall be readily available by end of the second business day and/or working day and shall identify all incidents of best management practices that have not been properly installed and/or maintained as described in the Plan. Where the report does not identify any incidents, the inspection report shall contain a certification that the best management practices are in compliance with the Erosion, Sedimentation and Pollution Control Plan. The report shall be signed in accordance with Part V.G.2. of this permit.

NO MATERIAL IS TO BE BURNED ON SITE. ALL WASTE MATERIAL SHALL BE DISPOSED OF AT A PERMITTED OFFSITE LANDFILL

THE INSTALLATION OF EROSION CONTROL MEASURES SHALL TAKE PLACE PRIOR TO OR CONCURRENT WITH LAND DISTURBING ACTIVITIES

ALL IMPROVEMENTS TO CONFORM WITH CLAY COUNTY CONSTRUCTION STANDARDS

NOTIFY CLAY COUNTY 24 HOURS BEFORE STARTING EACH PHASE OF CONSTRUCTION

MAXIMUM CUT OR FILL SLOPES ARE 2 HORIZONTAL TO 1 VERTICAL

ALL EROSION AND SEDIMENT CONTROL MEASURES WILL BE INSPECTED DAILY AND ANY DEFICIENCIES NOTED WILL BE CORRECTED BY THE END OF EACH DAY. ADDITIONAL EROSION CONTROL MEASURES WILL BE INSTALLED IF DEEMED NECESSARY BY ON-SITE INSPECTOR.

SITE AREA:16.22 AC

DISTURBED AREA:11.18 AC

EARTHWORK ESTIMATE:

CUT:45,158 CY

FILL:52,180 CY

DIFFERENCE: 7,022 CY *

*APPROXIMATELY 7,000 CY OF EARTHWORK TO BE TAKEN FROM DREDGING ACTIVITES TO BALANCE THE EARTHWORK.

*EARTHWORK CALCULATIONS ARE BASED ON FINISHED GRADE.

EARTHWORK ESTIMATE PROVIDED FOR CONVENIENCE TO CONTRACTOR ONLY. CONTRACTOR IS TO VERIFY QUANTITIES.

ADDITIONAL EROSION CONTROL NOTES:

THE DESIGN PROFESSIONAL WHO PREPARED THE ES&PC PLAN IS TO INSPECT THE INSTALLATION OF THE INITIAL SEDIMENT STORAGE REQUIREMENTS AND PERIMETER CONTROL BMPS WITHIN 7 DAYS AFTER INSTALLATION.

NON-EXEMPT ACTIVITIES SHALL NOT BE CONDUCTED WITHIN THE 25 OR 50-FOOT UNDISTURBED STREAM BUFFERS AS MEASURED FROM THE POINT OF WRESTED VEGETATION WITHOUT FIRST ACQUIRING THE NECESSARY VARIANCES AND PERMITS.

AMENDMENTS/REVISIONS TO THE ES&PC PLAN WHICH HAVE A SIGNIFICANT EFFECT ON BMPS WITH A HYDRAULIC COMPONENT MUST BE CERTIFIED BY THE DESIGN PROFESSIONAL.

WASTE MATERIALS SHALL NOT BE DISCHARGED TO WATERS OF THE STATE, EXCEPT AS AUTHORIZED BY A SECTION 404 PERMIT.

THE ESCAPE OF SEDIMENT FROM THE SITE SHALL BE PREVENTED BY THE INSTALLATION OF EROSION AND SEDIMENT CONTROL MEASURES AND PRACTICES PRIOR TO LAND DISTURBING ACTIVITIES.

EROSION CONTROL MEASURES WILL BE MAINTAINED AT ALL TIMES. IF FULL IMPLEMENTATION OF THE APPROVED PLAN DOES NOT PROVIDE FOR EFFECTIVE EROSION CONTROL, ADDITIONAL EROSION AND SEDIMENT CONTROL MEASURES SHALL BE IMPLEMENTED TO CONTROL OR TREAT THE SEDIMENT SOURCE.

ANY DISTURBED AREA LEFT EXPOSED FOR A PERIOD GREATER THAN 14 DAYS SHALL BE STABILIZED WITH MULCH OR TEMPORARY SEEDING.

DETENTION POND OR SEDIMENT BASIN / STORAGE WILL BE INSTALLED AND FUNCTIONING BEFORE ANY MAJOR GRADING OR IMPERVIOUS SURFACES ARE CONSTRUCTED.

NOTE:

MAINTENANCE OF ALL EROSION CONTROL MEASURES, WHETHER TEMPORARY OR PERMANENT, SHALL AT ALL TIMES BE THE RESPONSIBILITY OF THE OWNER.

SURFACE ROUGHENING:

ALL CUT AND FILL SLOPES SHALL BE SURFACED ROUGHENED AND VEGETATED WITHIN THREE (3) DAYS AFTER GRADING.

DISPOSAL:

STUMPS AND CONSTRUCTION DEBRIS SHALL BE DEPOSITED IN A PROPERLY PERMITTED LANDFILL.

TYPE "S" SILT FENCE:

A DOUBLE ROW OF TYPE "S" SILT FENCE SHALL BE REQUIRED WHEN PLACED WITHIN 200' OF STATE WATERS AND AT THE TOE OF SLOPES GREATER THAN 10' IN HEIGHT.

GRADING NOTES:

COMPACTON:

COMPACTION OF THE BACKFILL OF ALL TRENCHES SHALL BE COMPACTED TO THE DENSITY OF 95% OF MODIFIED PROCTOR MAXIMUM DENSITY PER A.S.T.M. TEST D-698. BACKFILL MATERIAL SHALL BE FREE FROM ROOTS, STUMPS, OR OTHER FOREIGN DEBRIS, AND SHALL BE PLACED AT OR NEAR OPTIMUM MOISTURE. CORRECTION OF ANY TRENCH SETTLEMENT WITHIN A YEAR FROM THE DATE OF APPROVAL WILL BE THE RESPONSIBILITY OF THE CONTRACTOR.

BEDDING:

ALL STORM DRAIN AND SANITARY SEWER PIPES SHALL HAVE A CLASS "C" BEDDING AS A MINIMUM UNLESS NOTED OTHERWISE. EXCAVATE AND SHAPE BOTTOM OF TRENCH TO THE PROPER GRADE AND TO FIT THE LOWER PART OF THE PIPE EXTERIOR FOR A WIDTH OF A LEAST 50 PERCENT OF THE OUTSIDE DIAMETER OF THE PIPE. SIDES AND AREA OVER THE PIPE SHALL THEN BE FILLED WITH COMPACTED BACKFILL.

PAVING:

PAVING SHALL BE DONE IN ACCORDANCE WITH THE SPECIFICATIONS PROVIDED IN THESE PLANS. ALL PAVEMENT WITHIN THE NCDOT R/W MUST CONFORM TO ALL NCDOT PAVING STANDARDS.

CONCRETE:

3000 PSI COMPRESSIVE STRENGTH AT 28 DAYS, REINFORCING BARS SHALL CONFORM TO THE REQUIREMENTS OF ASTM A 615 GRADE 60.

FIELD CONDITIONS:

CONTRACTOR SHALL VERIFY FIELD CONDITIONS AFFECTING CONSTRUCTION, PARTICULARLY UTILITIES, PRIOR TO CONSTRUCTION. CHANGES IN CONSTRUCTION NECESSITATED BY FIELD CONDITIONS SHALL BE APPROVED BY THE OWNER OR OWNER'S ENGINEER PRIOR TO CONSTRUCTION. IN ACCORDANCE WITH STATE LAW, THE CONTRACTOR SHALL CALL 800-288-7411 AT LEAST THREE (3) WORKING DAYS PRIOR TO CONSTRUCTION FOR LOCATION OF UNDERGROUND UTILITIES.

CONSTRUCTION STAKING:

CONSTRUCTION STAKING IS THE RESPONSIBILITY OF THE CONTRACTOR.

CONSTRUCTION NOTES:

1. NO ADDITIONAL CONSTRUCTION OR IMPROVEMENTS, INCLUDING BUT NOT LIMITED TO WALLS, FENCES, SIGNS, SPRINKLER SYSTEMS, LIGHTS, TRESS, ETC., WILL BE ALLOWED ON THE ROAD RIGHT-OF-WAY.

2. THE CLAY COUNTY SHALL BE NOTIFIED 24 HOURS PRIOR TO ANY CONSTRUCTION.

3. ALL WATER MATERIALS AND WORKMANSHIP SHALL BE IN ACCORDANCE WITH THE CLAY COUNTY WATER & SEWER DEPARTMENT.

4. THE CONTRACTOR SHALL BE RESPONSIBLE FOR MAINTAINING A MARKED-UP SET OF DESIGN DRAWINGS SHOWING ALL "ASBUILT" CONDITIONS. THESE "RECORD DRAWINGS" SHALL BE MADE AVAILABLE TO THE DESIGNER AND/OR THE CITY INSPECTOR UPON REQUEST. THE MARK-UPS SHALL BE AT THE SITE AT ALL TIMES AND SHALL BE UTILIZED TO DEVELOP FINAL RECORD DRAWINGS.

5. ANY CHANGES IN THE HORIZONTAL ALIGNMENT SHOWN HEREON SHALL BE APPROVED BY THE DESIGN ENGINEER AND THE CLAY COUNTY PRIOR TO CONSTRUCTION.

6. THE CONTRACTOR IS RESPONSIBLE FOR ALL UTILITY LOCATIONS. CONTRACTOR SHOULD NOTIFY THE UTILITIES PROTECTION CENTER, INC. AT (800) 282-7411 THREE WORKING DAYS BEFORE CONSTRUCTION IS TO BEGIN.

7. THE CONTRACTOR IS RESPONSIBLE FOR THE INSTALLATION & MAINTENANCE OF ALL REQUIRED SEDIMENT CONTROL STRUCTURES.

8. ALL DISTURBED AREAS SHALL BE GRASSED IMMEDIATELY UPON COMPLETION OF BACK FILLING TRENCHES.

9. CLEARING LIMITS SHALL BE CLEARLY DELINEATED WITH TREE SAVE FENCE OR OTHER SUITABLE MEANS.

10. CONTRACTOR IS RESPONSIBLE FOR THE ADJUSTMENTS TO ALL EXISTING UTILITIES ON SITE TO FINAL GRADE.

NOTES:

DISPOSAL: STUMPS AND CONSTRUCTION DEBRIS SHALL BE DEPOSITED IN A PROPERLY PERMITTED LANDFILL.

PIPE: STORM DRAIN PIPES WILL BE CLASS III REINFORCED CONCRETE PIPE (RCP), TYPE II ALUMINIZED CORRUGATED STEEL PIPE (AC20SP) OR HDPE.

THE HORIZONTAL DATUM FOR THIS SURVEY IS STATE PLANE NORTH CAROLINA (NAD83).

ALL DISTANCES SHOWN ARE HORIZONTAL GROUND DISTANCES IN U.S. SURVEY FEET. (39.37 INCHES = 1 METER)

EROSION CONTROL NARRATIVE

PURPOSE OF DEVELOPMENT:

THE PROPOSED PROJECT INVOLVES A RESIDENTIAL DEVELOPMENT INCLUDING 15 ATTACHED SINGLE FAMILY UNITS, AND 44 DETACHED SINGLE FAMILY UNITS.

SITE AND ADJACENT AREA CONDITIONS:

THE PROJECT SITE IS CURRENTLY A GRASSY FIELD ADJACENT TO LAKE CHATUGE, WITH WETLANDS THAT DRAIN DIRECTLY INTO THE LAKE. THE SITE IS BORDERED BY HIGHWAY 175 AND IS ADJACENT TO SEVERAL SINGLE-FAMILY RESIDENTIAL PROPERTIES.

PROPOSED EROSION AND SEDIMENT CONTROL MEASURES:

TO PREVENT SEDIMENT FROM ENTERING THE LAKE DURING CONSTRUCTION, A TURBIDITY CURTAIN WILL BE DEPLOYED WITHIN THE LAKE TO CONTAIN DISTURBED MATERIALS. A SILT FENCE WILL BE INSTALLED AROUND ALL DISTURBED AREAS TO INTERCEPT SEDIMENT RUNOFF. A STABILIZED CONSTRUCTION ENTRANCE WILL MINIMIZE OFF-SITE TRACKING OF SEDIMENT BY CONSTRUCTION VEHICLES. EXPOSED SOILS WILL BE STABILIZED PROMPTLY USING TEMPORARY SEEDING DURING CONSTRUCTION AND PERMANENT SEEDING UPON PROJECT COMPLETION TO ENSURE LONG-TERM EROSION CONTROL.

CONSTRUCTION SEQUENCE:

INSTALL EROSION CONTROLS:

SET UP THE CONSTRUCTION ENTRANCE, SILT FENCE, AND TURBIDITY CURTAIN BEFORE ANY LAND-DISTURBING ACTIVITIES.

DREDGING OPERATIONS:

PERFORM DREDGING WITHIN THE TURBIDITY CURTAIN, WORKING TO MINIMIZE THE TURBIDITY LEVELS OF THE WATER.

WASTE PLACEMENT:

DEPOSIT DREDGED MATERIAL ON-SITE ABOVE THE DOUBLE-ROW SILT FENCE IN DESIGNATED WASTE AREA.

SITE STABILIZATION:

STABILIZE DISTURBED AREAS AND BEGIN REVEGETATION IMMEDIATELY AFTER DREDGING AND WASTE PLACEMENT. ALL AREAS IN RIPARIAN BUFFER TO BE STABILIZED AT THE END OF THE WORK DAY.

REMOVE TEMPORARY CONTROLS:

AFTER STABILIZATION IS COMPLETE, REMOVE THE SILT FENCE, TURBIDITY CURTAIN, AND CONSTRUCTION ENTRANCE.

REVISION NUMBER	DATE	AFFECTED SHEETS	REVISION HISTORY CHART DESCRIPTION	P.E./ R.L.S. INITIAL

DATE	AGENCY	DEPARTMENT	SUBMITTAL HISTORY CHART DESCRIPTION	PERMIT TYPE	PERMIT NUMBER	APPROVAL DATE
04/28/25	CLAY COUNTY	PLANNING DIVISION	1st PLAN SUBMITTAL	LDP		

ANY CHANGES OR ALTERATIONS MADE TO THIS DRAWING SHALL BE INDICATED BY A REVISION NUMBER AND DATE. IT IS THE RESPONSIBILITY OF THE CONTRACTOR TO OBTAIN THE WRITTEN APPROVAL OF ROCHESTER & ASSOCIATES, INC. BEFORE ANY CHANGES TO THE ORIGINAL DRAWINGS ARE KEPT ON FILE FOR VERIFICATION OF ANY CHANGES.

1ST SUBMITTAL

GENERAL NOTES

FOR:

STONE BRIDGE

RESIDENTIAL SUBDIVISION

LOCATED IN:

HAWASSEE TOWNSHIP

CLAY COUNTY, NORTH CAROLINA

REVISIONS

NO.	DATE	DESCRIPTION

SHEET

2

OF

31

DATE: 04/28/25

SCALE: N.T.S.

JOB NO. 25056 TMM

DRAWN BY: CSM

CHECKED BY: CMA


Rochester


Engineering, Inc.

Rochester Engineering, INC.

425 Oak St NW, Gainesville, GA 30601

770.718.0600 | rochester.dccm.com







LOT CHART			
	EAST PARCEL	WEST PARCEL	TOTAL
ATTACHED UNITS	15	0	15
DETACHED UNITS	33	12	45
TOTAL	48	12	60

DENSITY CHART			
	ACREAGE	# OF UNITS	UNITS PER ACRE
EAST PARCEL	10.98 AC	48	4.37
WEST PARCEL	5.23 AC	12	2.29
TOTAL	16.22 AC	60	3.70


THE PROPOSED DEVELOPMENT INCLUDES A TOTAL OF 60 RESIDENTIAL UNITS, CONSISTING OF 48 DETACHED UNITS AND 12 ATTACHED UNITS. SITE AMENITIES INCLUDE GOLF CART GARAGES, A COMMUNITY POOL, BEACH AREA, PAVILION, WALKING TRAIL, LAGOON, AND MULTIPLE PICKLEBALL COURTS.

TOTAL PARKING: 82 SPACES
GOLF CART GARAGES: 17 GARAGES







SIGN LEGEND



"YIELD" SIGN
30"x36"
M.U.T.C.D. R1-2




"STOP" SIGN
30"x30"
M.U.T.C.D. R1-1



"SPEED LIMIT 20 MPH" SIGN
24"x30"
M.U.T.C.D. R2-1

NOTE: ALL SIGNAGE & STRIPING IS TO BE PER M.U.T.C.D. & NCDOT STANDARDS



NO.	DATE	DESCRIPTION

ANY CHANGES OR ALTERATIONS MADE TO THIS DRAWING SHALL BE THE RESPONSIBILITY OF THE CLIENT. THE WRITTEN APPROVAL OF ROCHESTER ENGINEERING, INC. IS REQUIRED FOR ANY CHANGES TO BE MADE TO THIS DRAWING. ORIGINAL DRAWINGS ARE KEPT ON FILE FOR VERIFICATION OF ANY CHANGES.


GRAPHIC SCALE: 1" = 60'

30' 0' 60' 120'

1ST SUBMITTAL

SHEET
5
OF
31

DATE: 04/28/25
SCALE: 1" = 60'
JOB NO.: 25056 TMM
DRAWN BY: CWS
CHECKED BY: CWS





Rochester Engineering, Inc.
Rochester Engineering, Inc.
425 Oak St NW, Gainesville, GA 30501
770.718.0600 | rochester.dccm.com

ENTRANCE PLAN FOR:
**STONE BRIDGE
RESIDENTIAL SUBDIVISION**

LOCATED IN:
HAWASSEE TOWNSHIP
CLAY COUNTY, NORTH CAROLINA

ANY CHANGES OR ALTERATIONS MADE TO THIS DRAWING SHALL BE THE RESPONSIBILITY OF THE CLIENT. THE WRITTEN APPROVAL OF ROCHESTER ENGINEERING, INC. IS REQUIRED FOR ANY CHANGES TO BE MADE TO THIS DRAWING. THE ORIGINAL DRAWINGS ARE KEPT ON FILE FOR VERIFICATION OF ANY CHANGES.



NO.	DATE	DESCRIPTION	REVISIONS

GRAPHIC SCALE
5' 0' 10' 20'

1ST SUBMITTAL

SHEET
6
OF
31

DATE: 04/28/25
SCALE: 1" = 10'
JOB NO. 2506 TMM
DRAWN BY: CWS
CHECKED BY: CWS
DRAWN BY: CWS




Rochester Engineering, Inc.
Rochester Engineering, Inc.
425 Oak St NW, Gainesville, GA 30501
770.718.0600 | rochester.dccm.com

FOR:
**STONE BRIDGE
RESIDENTIAL SUBDIVISION**

LOCATED IN:
HAWASSEE TOWNSHIP
CLAY COUNTY, NORTH CAROLINA


REVISIONS		NO.	DATE	DESCRIPTION

ANY CHANGES OR ALTERATIONS MADE TO THIS DRAWING SHALL BE THE RESPONSIBILITY OF THE CLIENT. THE WRITTEN APPROVAL OF ROCHESTER ENGINEERING, INC. (DCCM) IS REQUIRED FOR ANY CHANGES TO BE MADE TO THIS DRAWING. ORIGINAL DRAWINGS ARE KEPT ON FILE FOR VERIFICATION OF ANY CHANGES.



1ST SUBMITTAL

SHEET	7
OF	31
DATE:	04/28/25
SCALE:	1" = 60'
DRAWN BY:	CNS
CHECKED BY:	CNS
DESIGNED BY:	CNS
IN CHARGE:	CNS



*EARTHWORK CALCULATIONS ARE BASED ON FINISHED GRADE

EARTHWORK ESTIMATE PROVIDED FOR CONVENIENCE TO CONTRACTOR ONLY.
CONTRACTOR IS TO VERIFY QUANTITIES.



GRADING PLAN
FOR:
**STONE BRIDGE
RESIDENTIAL SUBDIVISION**

[illegible]


ANY CHANGES OR ALTERATIONS MADE TO THESE CONSTRUCTION DRAWINGS WITHOUT THE WRITTEN APPROVAL OF ROCHESTER INDOCCM VIOLATES THE SEAL SHOWN HEREON. ANY LIABILITY ASSOCIATED WITH THIS PROJECT OR ORIGINAL DRAWINGS ARE KEPT ON FILE FOR VERIFICATION OF ANY CHANGES.







1ST SUBMITTAL

SHEET
8
OF
31

DATE: 04/28/25
SCALE: 1" = 60'
JOB NO. G224096.TNM
WG NO. .CNST.dwg





FOR:
STONE BRIDGE
RESIDENTIAL SUBDIVISION

NO.	DATE	DESCRIPTION



ANY CHANGES OR ALTERATIONS MADE TO THIS DRAWING SHALL BE THE RESPONSIBILITY OF THE ENGINEER. THE WRITTEN APPROVAL OF ROCHESTER ENGINEERING, INC. IS REQUIRED FOR ANY CHANGES. ORIGINAL DRAWINGS ARE KEPT ON FILE FOR VERIFICATION OF ANY CHANGES.




GRAPHIC SCALE
25' 0' 50' 100'


1ST SUBMITTAL

SHEET	10
OF	31


DATE: 04/28/25
JOB NO.: 2025 TMM
DRAWN BY: CMA
CHECKED BY: CMA








N/F
JOEL E. RAE &
BRENDA G. RAE
(DB 392, PG 200)
(PB 3, PG 194)



Sight Distance Road A



Sight Distance Road F

SIGHT DISTANCE CERTIFICATION

I, THE UNDERSIGNED, HEREBY CERTIFY THE SIGHT DISTANCE FOR THE PROJECT IS DESIGNED WITH ADEQUATE DISTANCE. THE REGULATED SPEED LIMIT ON THE APPROACHING THOROUGHFARE IS 45 MPH. THE DESIGNED SIGHT DISTANCE PROVIDES VISIBILITY OF 450 FEET TO THE LEFT AND 450 FEET TO THE RIGHT. THE SIGHT DISTANCE SHALL BE MEASURED FROM A POINT OF 15 FEET FROM TRAVEL LANE AT AN EYE LEVEL OF 3.5 FEET AND LOOKING AT AN OBJECT 3.5 FEET ABOVE THE CENTERLINE.

SIGNED AND SEALED _____ 1ST SUBMITTAL
DATE _____





FOR:
**STONE BRIDGE
RESIDENTIAL SUBDIVISION**
LOCATED IN:
HAWASSEE TOWNSHIP
CLAY COUNTY, NORTH CAROLINA

ANY CHANGES OR ALTERATIONS MADE TO THIS DRAWING WITHOUT THE WRITTEN APPROVAL OF ROCHESTER ENGINEERING, INC. VOID THE SEAL SHOWN HEREON AND THE ENGINEER'S RESPONSIBILITY FOR THE ORIGINAL DRAWINGS ARE KEPT ON FILE FOR VERIFICATION OF ANY CHANGES.

1ST SUBMITTAL

SHEET
13
OF
31
DATE: 04/28/25
SCALE: 1"=50'
JOB NO.: 2505 TMM
DRAWN BY: CWS
CHECKED BY: CWS
DESIGNED BY: CWS
DRAWN BY: CWS



Rochester Engineering, Inc.
Rochester Engineering, Inc.
425 Oak St NW, Gainesville, GA 30501
770.718.0600 | rochester.dccm.com

FOR:
**STONE BRIDGE
RESIDENTIAL SUBDIVISION**

LOCATED IN:
HAWASSEE TOWNSHIP
CLAY COUNTY, NORTH CAROLINA




REVISIONS		NO.	DATE	DESCRIPTION

ANY CHANGES OR ALTERATIONS MADE TO THIS DRAWING SHALL BE THE RESPONSIBILITY OF THE CLIENT. THE WRITTEN APPROVAL OF ROCHESTER ENGINEERING, INC. IS REQUIRED FOR ANY CHANGES TO BE MADE TO THIS DRAWING. ORIGINAL DRAWINGS ARE KEPT ON FILE FOR VERIFICATION OF ANY CHANGES.

1ST SUBMITTAL

SHEET
14
OF
31

DATE: 04/28/25
SCALE: 1" = 60'
JOB NO.: 2505 TMM
DRAWN BY: CWS
CHECKED BY: CWS



Rochester Engineering, Inc.
Rochester Engineering, Inc.
425 Oak St NW, Gainesville, GA 30501
770.718.0600 | rochester.dccm.com

FOR:
STONE BRIDGE
RESIDENTIAL SUBDIVISION

LOCATED IN:
HAWASSEE TOWNSHIP
CLAY COUNTY, NORTH CAROLINA







ANY CHANGES OR ALTERATIONS MADE TO
THIS DRAWING SHALL BE THE RESPONSIBILITY
OF THE WRITER. THE WRITER'S SEAL AND
DCCM VOIDS THE SEAL SHOWN HEREON AND
THE WRITER'S SEAL SHALL BE KEPT ON FILE FOR
VERIFICATION OF ANY CHANGES.

GRAPHIC SCALE
25' 0' 50' 100'


1ST SUBMITTAL

SHEET
15
OF
31

DATE: 04/28/25
JOB NO.: 25056 TMM
DRAWN BY: CSM
CHECKED BY: CSM





NO.	DATE	DESCRIPTION



1ST SUBMITTAL





Rochester Engineering, Inc.
Rochester Engineering, Inc.
425 Oak St NW, Gainesville, GA 30501
770.718.0600 | rochester.dccm.com

FOR:
**STONE BRIDGE
RESIDENTIAL SUBDIVISION**

LOCATED IN:
HIAMASSEE TOWNSHIP
CLAY COUNTY, NORTH CAROLINA

NO.	DATE	DESCRIPTION	REVISIONS



ANY CHANGES OR ALTERATIONS MADE TO THIS DRAWING SHALL BE THE RESPONSIBILITY OF THE DESIGNER. THE WRITTEN APPROVAL OF ROCHESTER ENGINEERING, INC. IS REQUIRED FOR ANY CHANGES TO BE MADE TO THIS DRAWING. ORIGINAL DRAWINGS ARE KEPT ON FILE FOR VERIFICATION OF ANY CHANGES.

GRAPHIC SCALE: 1"=50'
25' 0' 50' 100'

1ST SUBMITTAL

SHEET
18
OF
31

DATE: 04/28/25
SCALE: 1"=50'
JOB NO.: 25056 TMM
DESIGNED BY: CANS
DRAWN BY: CMA



inletID	LineSize	LineLength	LineSlope	n-value	Pipe	DrainageArea	RunoffCoeff	InletTime	Tc	inlet	iS	IncrQ	KnownQ	TotalRunoff	VelDn
	(in)	(ft)	(%)			(ac)	(C)	(min)	(min)	(in/hr)	(in/hr)	(cfs)	(cfs)	(cfs)	(ft/s)
8B	42	58.11	0.50	0.01		0.00	0.76	5.00	11.20	0.00	5.99	0.00	0.00	26.10	5.81
8C	42	66.21	0.50	0.01		0.13	0.76	5.00	11.00	7.63	6.03	0.74	0.00	26.30	7.64
9A	30	37.75	0.53	0.01		0.18	0.76	5.00	10.90	7.63	6.06	1.04	0.00	21.39	7.53
9B	30	26.01	1.00	0.01		0.12	0.76	5.00	10.80	7.63	6.08	0.70	0.00	20.63	6.35
1A	30	101.83	14.00	0.01		0.05	0.76	5.00	10.40	7.63	6.16	0.29	0.00	19.83	6.25
1B	24	77.98	5.59	0.01		0.11	0.76	5.00	10.20	7.63	6.20	0.64	0.00	19.73	17.77
1C	24	129.29	11.90	0.01		0.10	0.76	5.00	9.80	7.63	6.28	0.58	0.00	17.55	6.57
1D	18	76.27	8.90	0.01		0.22	0.76	5.00	9.50	7.63	6.36	1.28	0.00	6.26	14.64
1E	18	108.97	9.40	0.01		0.09	0.76	5.00	8.90	7.63	6.49	0.52	0.00	5.30	4.51
1F	18	30.83	14.00	0.01		0.00	0.76	5.00	8.80	0.00	6.53	0.00	0.00	4.89	4.33
1G	18	30.83	14.00	0.01		0.00	0.76	5.00	8.60	0.00	6.57	0.00	0.00	4.92	16.06
1H	18	30.83	14.00	0.01		0.00	0.76	5.00	8.40	0.00	6.62	0.00	0.00	4.95	16.08
1J	18	47.86	3.09	0.01		0.30	0.76	5.00	8.20	7.63	6.68	1.74	0.00	5.00	9.41
1I	18	75.46	6.60	0.01		0.19	0.76	5.00	7.60	7.63	6.83	1.10	0.00	3.56	3.13
1K	18	17.88	1.00	0.01		0.27	0.76	5.00	7.40	7.63	6.89	1.54	0.00	2.59	3.04
1L	18	108.55	5.00	0.01		0.23	0.76	5.00	5.00	7.63	7.63	1.33	0.00	1.33	2.02
4A	18	20.07	2.00	0.01		0.27	0.76	5.00	7.20	7.63	6.94	1.57	0.00	12.02	9.97
4B	18	15.69	14.02	0.01		0.28	0.76	5.00	7.20	7.63	6.95	1.62	0.00	10.61	6.47
4C	18	131.77	14.00	0.01		0.34	0.76	5.00	6.70	7.63	7.09	1.97	0.00	8.19	5.20
4D	18	115.37	9.90	0.01		0.13	0.76	5.00	6.20	7.63	7.24	0.75	0.00	6.50	15.37
4E	18	71.13	5.61	0.01		0.25	0.76	5.00	5.80	7.63	7.36	1.43	0.00	5.87	4.77
4F	18	107.33	11.69	0.01		0.14	0.76	5.00	5.10	7.63	7.58	0.81	0.00	4.63	4.00
4G	18	17.88	2.01	0.01		0.66	0.76	5.00	5.00	7.63	7.63	3.85	0.00	3.85	3.86
5A	18	17.88	7.72	0.01		0.21	0.76	5.00	5.00	7.63	7.63	1.22	0.00	1.22	0.89
5A	18	43.71	2.00	0.01		0.15	0.76	5.00	5.00	7.63	7.63	0.87	0.00	0.87	4.84
2A	18	18.92	1.00	0.01		0.25	0.76	5.00	5.00	7.63	7.63	1.45	0.00	1.45	4.42
8D	30	129.08	1.34	0.01		0.10	0.76	5.00	5.70	7.63	7.41	0.56	0.00	3.08	10.24
8E	30	55.45	2.63	0.01		0.45	0.76	5.00	5.50	7.63	7.47	2.61	0.00	2.56	6.07
8F	30	79.93	2.70	0.01		0.00	0.76	5.00	5.10	0.00	0.00	0.00	0.00	0.00	6.04
8G	30	35.44	12.61	0.01		0.00	0.76	5.00	5.00	0.00	0.00	20.48	20.48	0.00	6.48
7B	42	111.14	0.50	0.01		0.00	0.76	5.00	7.30	0.00	6.90	0.00	0.00	10.07	9.06
13A	24	58.28	0.50	0.01		0.00	0.76	5.00	7.00	0.00	6.98	0.00	0.00	10.19	5.39
13B	24	14.13	0.50	0.01		0.33	0.76	5.00	7.00	7.63	7.00	1.91	0.00	10.22	5.51
13C	18	168.03	0.50	0.01		0.16	0.76	5.00	5.50	7.63	7.47	0.93	0.00	3.24	4.30
15A	18	37.80	2.14	0.01		0.41	0.76	5.00	5.00	7.63	7.63	2.38	0.00	2.38	6.68
14A	18	17.90	1.01	0.01		1.02	0.76	5.00	5.00	7.63	7.63	5.92	0.00	5.92	6.51
9C	18	65.12	1.00	0.01		0.11	0.76	5.00	5.00	7.63	7.63	0.64	0.00	0.64	1.11
7C	42	122.60	0.50	0.01		0.00	0.76	5.00	5.20	0.00	0.00	0.00	0.00	0.00	7.76
7D	42	70.80	1.30	0.01		0.00	0.76	5.00	5.00	0.00	0.00	59.92	59.92	0.00	8.43
6B	24	30.31	0.50	0.01		0.25	0.76	5.00	5.60	7.63	7.14	1.45	0.00	11.99	4.01
6C	18	39.69	5.87	0.01		0.10	0.76	5.00	6.40	7.63	7.18	0.58	0.00	10.69	12.24
6D	18	95.50	0.50	0.01		0.19	0.76	5.00	6.10	7.63	7.27	1.10	0.00	10.27	5.81
6E	18	50.07	0.50	0.01		0.19	0.76	5.00	5.90	7.63	7.32	1.10	0.00	9.29	5.26
6F	18	80.19	0.50	0.01		0.31	0.76	5.00	5.70	7.63	7.41	1.80	0.00	8.33	4.72
6G	18	62.50	1.30	0.01		0.17	0.76	5.00	5.40	7.63	7.50	0.99	0.00	6.67	3.78
8H	18	74.50	1.50	0.01		1.00	0.76	5.00	5.00	7.63	7.63	5.80	0.00	5.80	3.28
10A	18	47.90	0.50	0.01		0.23	0.76	5.00	5.50	7.63	7.47	1.33	0.00	2.38	3.97
10B	18	17.88	0.50	0.01		0.19	0.76	5.00	5.00	7.63	7.63	1.10	0.00	1.10	1.73


[illegible]

ANY CHANGES OR ALTERATIONS MADE TO THESE CONSTRUCTION DRAWINGS WITHOUT THE SEAL, SIGNATURE AND EXPIRATION DATE OF THE PROFESSIONAL ENGINEER SHALL VOID THE SEAL. NO LIABILITY ASSOCIATED WITH THIS PROJECT OR ORIGINAL DRAWINGS ARE KEPT ON FILE FOR VERIFICATION OF ANY CHANGES.

GRAPHIC SCALE

25' 0' 50' 100'

1ST SUBMITTAL



Rochester Engineering, INC.
425 Oak St NW, Gainesville, GA 30501
770.718.0600 | rochester.dccm.com

LOCATED IN
HIAWASSEE TOWNSHIP
CLAY COUNTY, NORTH CAROLINA



ANY CHANGES OR ALTERATIONS MADE TO THESE CONSTRUCTION DRAWINGS WITHOUT THE SEAL, SIGNATURE AND EXPIRATION DATE OF THE PROFESSIONAL ENGINEER OR ARCHITECT SHALL VOID THE SEAL, SIGNATURE AND EXPIRATION DATE OF THE PROFESSIONAL ENGINEER OR ARCHITECT. ANY LIABILITY ASSOCIATED WITH THIS PROJECT OR ORIGINAL DRAWINGS ARE KEPT ON FILE FOR VERIFICATION OF ANY CHANGES.

GRAPHIC SCALE

30' 0' 60' 120'

SHEET
20
OF
31

DATE: 04/28/25
SCALE: 1" = 60'
JOB NO. G224096.TNM
DWG NO. .CNST.dwg
DRAWN BY: CMM



SANITARY SEWER PLAN & PROFILE
FOR:
STONE BRIDGE
RESIDENTIAL SUBDIVISION

NO.	DATE	DESCRIPTION





ANY CHANGES OR ALTERATIONS MADE TO THIS DRAWING SHALL BE THE RESPONSIBILITY OF THE CLIENT. THE WRITTEN APPROVAL OF ROCHESTER ENGINEERING, INC. IS REQUIRED FOR ANY CHANGES TO BE MADE TO THIS DRAWING. ORIGINAL DRAWINGS ARE KEPT ON FILE FOR VERIFICATION OF ANY CHANGES.

1ST SUBMITTAL

SHEET
21
OF
31

DATE: 04/28/25
SCALE: 1" = 50'
DRAWN BY: CANS
CHECKED BY: CANS
DESIGNED BY: CANS
APPROVED BY: CANS

Rochester Engineering, Inc.
Rochester Engineering, Inc.
425 Oak St NW, Gainesville, GA 30501
770.718.0600 | rochester.dccm.com





NO.	DATE	DESCRIPTION	REVISIONS

ANY CHANGES OR ALTERATIONS MADE TO THIS DRAWING SHALL BE THE RESPONSIBILITY OF THE CLIENT. THE WRITTEN APPROVAL OF ROCHESTER ENGINEERING, INC. IS REQUIRED FOR ANY CHANGES TO BE MADE TO THIS DRAWING. ORIGINAL DRAWINGS ARE KEPT ON FILE FOR VERIFICATION OF ANY CHANGES.

GRAPHIC SCALE
25' 0' 50' 100'

1ST SUBMITTAL



Rochester Engineering, Inc.
Rochester Engineering, Inc.
425 Oak St NW, Gainesville, GA 30501
770.718.0600 | rochester.dccm.com

SANITARY SEWER PLAN & PROFILE
FOR:
STONE BRIDGE
RESIDENTIAL SUBDIVISION
LOCATED IN:
HAWASSEE TOWNSHIP
CLAY COUNTY, NORTH CAROLINA


NO.	DATE	DESCRIPTION	REVISIONS

ANY CHANGES OR ALTERATIONS MADE TO THIS DRAWING SHALL BE THE RESPONSIBILITY OF THE CLIENT. IT IS THE WRITTEN APPROVAL OF ROCHESTER ENGINEERING, INC. THAT THE SEAL SHOWN HEREON AND THE ORIGINAL DRAWINGS ARE KEPT ON FILE FOR VERIFICATION OF ANY CHANGES.


GRAPHIC SCALE: 25' 0' 50' 100'

1ST SUBMITTAL

SHEET
23
OF
31
DATE: 04/28/25
SCALE: 1"=50'
JOB NO.: 25056 TMM
DRAWN BY: CMA
CHECKED BY: CMA



NOTE: DUST CONTROL AS NECESSARY



LEGEND

- X — X — SILT FENCE
- O — O — TREE SAVE FENCE
- — — — — LIMITS OF DISTURBANCE
- — — — — TEMP. DIVERSION
- ● ● ● ● SOIL DELINEATION LINE

Rochester Engineering, Inc.
Rochester Engineering, Inc.
425 Oak St NW, Gainesville, GA 30501
770.718.0600 | rochester.dccm.com

FOR:
**STONE BRIDGE
RESIDENTIAL SUBDIVISION**

INITIAL EROSION CONTROL PLAN

LOCATED IN:
HAWASSEE TOWNSHIP
CLAY COUNTY, NORTH CAROLINA

NO.	DATE	DESCRIPTION	REVISIONS

ANY CHANGES OR ALTERATIONS MADE TO THIS DRAWING SHALL BE THE RESPONSIBILITY OF THE CLIENT. THE WRITTEN APPROVAL OF ROCHESTER ENGINEERING, INC. IS REQUIRED FOR ANY CHANGES TO BE MADE TO THIS DRAWING. ORIGINAL DRAWINGS ARE KEPT ON FILE FOR VERIFICATION OF ANY CHANGES.



GRAPHIC SCALE: 1" = 60'

1ST SUBMITTAL

SHEET
24
OF
31

DATE: 04/28/25
SCALE: 1" = 60'
JOB NO.: 2505 TMM
DRAWN BY: CSM
CHECKED BY: CSM

NOTE: DUST CONTROL AS NECESSARY



Rochester Engineering, Inc.
Rochester Engineering, Inc.
425 Oak St NW, Gainesville, GA 30501
770.718.0600 | rochester.dccm.com

FOR:
**STONE BRIDGE
RESIDENTIAL SUBDIVISION**
LOCATED IN:
HAWASSEE TOWNSHIP
CLAY COUNTY, NORTH CAROLINA


NO.	DATE	DESCRIPTION	REVISIONS

ANY CHANGES OR ALTERATIONS MADE TO THIS DRAWING SHALL BE THE RESPONSIBILITY OF THE CLIENT. THE WRITTEN APPROVAL OF ROCHESTER ENGINEERING, INC. IS REQUIRED FOR ANY CHANGES TO BE MADE TO THIS DRAWING. ORIGINAL DRAWINGS ARE KEPT ON FILE FOR VERIFICATION OF ANY CHANGES.


GRAPHIC SCALE
30' 0' 60' 120'

1ST SUBMITTAL

SHEET
25
OF
31
DATE: 04/28/25
SCALE: 1" = 60'
JOB NO.: 2505 TMM
DRAWN BY: CANS
CHECKED BY: CANS
DRAWN BY: CANS



NOTE:
UPON FINAL SITE STABILIZATION ALL TEMPORARY EROSION CONTROL
MEASURES ARE TO BE REMOVED AND DISPOSED OF PROPERLY.



LEGEND

- X — SILT FENCE
- O — TREE SAVE FENCE
- — — LIMITS OF DISTURBANCE
- TEMP. DIVERSION
- SOIL DELINEATION LINE

Rochester Engineering, Inc.
Rochester Engineering, Inc.
425 Oak St NW, Gainesville, GA 30501
770.718.0600 | rochester.dccm.com

FOR:
**STONE BRIDGE
RESIDENTIAL SUBDIVISION**

LOCATED IN:
HAWASSEE TOWNSHIP
CLAY COUNTY, NORTH CAROLINA

NO.	DATE	DESCRIPTION



ANY CHANGES OR ALTERATIONS MADE TO
THIS DRAWING MUST BE APPROVED BY THE
DESIGNER. THE WRITTEN APPROVAL OF ROCHESTER
ENGINEERING, INC. IS REQUIRED. ANY CHANGES
TO THE ORIGINAL DRAWINGS ARE KEPT ON FILE FOR
VERIFICATION OF ANY CHANGES.

GRAPHIC SCALE
30' 0' 60' 120'


1ST SUBMITTAL

SHEET
26
OF
31

DATE: 04/28/25
SCALE: 1" = 60'
JOB NO.: 2506 TMM
DRAWN BY: CWS
CHECKED BY: CWS
DESIGNED BY: CWS
DRAWN BY: CWS

DATE: _____			PAGE: _____																							
<p>SPACING GUIDE FOR SLOPE BREAKS</p> <table> <tr> <th></th><th>SLOPE</th><th>SPACING (FT)</th></tr> <tr> <td rowspan="3">Steep Slopes</td><td>2:1</td><td>20</td></tr> <tr> <td>3:1</td><td>35</td></tr> <tr> <td>4:1</td><td>45</td></tr> <tr> <td rowspan="5">Long Slopes</td><td>15-25%</td><td>50</td></tr> <tr> <td>10-15%</td><td>80</td></tr> <tr> <td>6-10%</td><td>125</td></tr> <tr> <td>3-6%</td><td>200</td></tr> <tr> <td><3%</td><td>300</td></tr> </table>							SLOPE	SPACING (FT)	Steep Slopes	2:1	20	3:1	35	4:1	45	Long Slopes	15-25%	50	10-15%	80	6-10%	125	3-6%	200	<3%	300
	SLOPE	SPACING (FT)																								
Steep Slopes	2:1	20																								
	3:1	35																								
	4:1	45																								
Long Slopes	15-25%	50																								
	10-15%	80																								
	6-10%	125																								
	3-6%	200																								
	<3%	300																								
<p>Use slope breaks, such as diversions, wattles, or benches, as appropriate, to reduce the length of cut-and-fill slope to limit sheet and rill erosion and prevent gullying.</p>																										
<p>MAINTENANCE:</p> <ol style="list-style-type: none"> Periodically check all graded areas and the supporting erosion and sedimentation control practices, especially after heavy rainfalls. Promptly remove all sediment from diversions and other water-disposal practices. If washouts or breaks occur, repair immediately. Prompt maintenance of small eroded areas before they become significant gullies is an essential part of an effective erosion and sedimentation control plan. 																										
<p>NOTES:</p> <ol style="list-style-type: none"> Construct and maintain all erosion and sediment control practices and measures in accordance with the approved sedimentation control plan and construction schedule. Remove good topsoil from areas to be graded and filled, and preserve it for use in finishing the grading of all critical areas. Scarify areas to be topsoiled to a minimum depth of 2 inches before placing topsoil. Clear and grub areas to be filled by removing trees, vegetation, roots, or other objectionable material that would affect the planned stability of the fill. Ensure that fill material is free of brush, rubbish, rocks, logs, stumps, building debris, and other materials inappropriate for constructing stable fills. Place all fill in layers not to exceed 9 inches in thickness, and compact the layers as required to reduce erosion, slippage, settlement, or other related problems. Do not incorporate frozen, soft, mucky, or highly compressible materials into a frozen foundation, due to possible subsidence and slippage. Do not place fill on a frozen foundation, due to possible subsidence and slippage. Keep diversions and other water conveyance measures free of sediment during all phases of development. Handle seeps or springs encountered during construction in accordance with approved methods (subsurface drain). Permanently stabilize all graded areas immediately after final grading is completed on each area in the grading plan. Apply temporary stabilization measures on all graded areas when work is to be interrupted or delayed for 30 days or longer. Show topsoil, stockpiles, borrow areas, and spoil areas on the plans, and make sure they are adequately protected from erosion. Include final stabilization of these areas in the plan. 																										
			<p>LAND GRADING</p>																							
			<p>Effective Date: 9/1/2023 In accordance with the 2013 Design Manual Updates</p>																							

DATE: _____	PAGE: _____																													
NON-INVASIVE PERMANENT SEEDING RECOMMENDATIONS FOR LATE WINTER AND EARLY SPRING	NON-INVASIVE PERMANENT SEEDING RECOMMENDATIONS FOR SUMMER	NON-INVASIVE PERMANENT SEEDING RECOMMENDATIONS FOR FALL																												
SEEDING MIXTURE <table border="1"> <thead> <tr> <th>Species</th><th>Rate</th></tr> </thead> <tbody> <tr> <td>Centipede</td><td>5 lbs/acre</td></tr> <tr> <td>Indian Woodoats</td><td>1.5-2.5 lbs/acre*</td></tr> <tr> <td>Virginia Wild Ryegrass</td><td>4-6 lbs/acre</td></tr> </tbody> </table> <p>*Depending upon mix with other species. See table 6.11.d from Chapter 6 of the NC Erosion and Sediment Control Planning and Design Manual.</p>	Species	Rate	Centipede	5 lbs/acre	Indian Woodoats	1.5-2.5 lbs/acre*	Virginia Wild Ryegrass	4-6 lbs/acre	SEEDING MIXTURE <table border="1"> <thead> <tr> <th>Species</th><th>Rate</th></tr> </thead> <tbody> <tr> <td>Indian Woodoats</td><td>1.5-2.5 lbs/acre*</td></tr> <tr> <td>Virginia Wild Ryegrass</td><td>4-6 lbs/acre*</td></tr> </tbody> </table> <p>*Depending upon mix with other species. See table 6.11.d from Chapter 6 of the NC Erosion and Sediment Control Planning and Design Manual.</p>	Species	Rate	Indian Woodoats	1.5-2.5 lbs/acre*	Virginia Wild Ryegrass	4-6 lbs/acre*	SEEDING MIXTURE <table border="1"> <thead> <tr> <th>Species</th><th>Rate</th></tr> </thead> <tbody> <tr> <td>Hard Fescue</td><td>15 lbs/acre</td></tr> <tr> <td>Switchgrass</td><td>2.5-3.5 lbs/acre*</td></tr> <tr> <td>Indian Grass</td><td>5-7 lbs/acre*</td></tr> <tr> <td>Big Bluestem</td><td>5-7 lbs/acre*</td></tr> <tr> <td>Indian Woodoats</td><td>1.5-2.5 lbs/acre*</td></tr> <tr> <td>Virginia Wild Ryegrass</td><td>4-6 lbs/acre*</td></tr> </tbody> </table> <p>*Depending upon mix with other species. See table 6.11.d from Chapter 6 of the NC Erosion and Sediment Control Planning and Design Manual.</p>	Species	Rate	Hard Fescue	15 lbs/acre	Switchgrass	2.5-3.5 lbs/acre*	Indian Grass	5-7 lbs/acre*	Big Bluestem	5-7 lbs/acre*	Indian Woodoats	1.5-2.5 lbs/acre*	Virginia Wild Ryegrass	4-6 lbs/acre*
Species	Rate																													
Centipede	5 lbs/acre																													
Indian Woodoats	1.5-2.5 lbs/acre*																													
Virginia Wild Ryegrass	4-6 lbs/acre																													
Species	Rate																													
Indian Woodoats	1.5-2.5 lbs/acre*																													
Virginia Wild Ryegrass	4-6 lbs/acre*																													
Species	Rate																													
Hard Fescue	15 lbs/acre																													
Switchgrass	2.5-3.5 lbs/acre*																													
Indian Grass	5-7 lbs/acre*																													
Big Bluestem	5-7 lbs/acre*																													
Indian Woodoats	1.5-2.5 lbs/acre*																													
Virginia Wild Ryegrass	4-6 lbs/acre*																													
Seeding Dates Coastal or Eastern Piedmont for Centipede- Sept. 1 - May 1 Coastal and Piedmont for Indian Woodoats and Virginia Wild Ryegrass- Feb 15 - April 1 Mountains for Indian Woodoats and Virginia Wild Ryegrass- March 1 - May 15	Seeding Dates Mountains - July 15- Aug 15 Piedmont - Aug 15 - Oct 15	Seeding Dates Mountains - Hard Fescue- Aug 1 - June 1 Mountains- Switchgrass, Indian Grass, Big Bluestem- Dec 1 - April 15 Piedmont and Coastal- Switchgrass, Indian Grass, Big Bluestem- Dec 1 - April 1 Coastal- Indian Woodoats and Virginia Wild Ryegrass- Sept 1 - Nov 1																												
Maintenance: Significant maintenance may be required to obtain desired cover.	Maintenance: Indian Woodoats and Virginia Wild Ryegrass are both sun and shade tolerant.	Maintenance: Fescue is not recommended for slopes > 5%. Prefers shade.																												
SEED BED PREPARATION:																														
LIMING: Apply lime according to soil test recommendations. If the pH (acidity) of the soil is not known, an application of ground agricultural limestone at the rate of 1 to 1½ tons/acre on coarse/textured soils and 2-3 tons/acre on fine-textured soils is usually sufficient. Apply limestone uniformly and incorporate into the top 4-6 inches of soil. Soils with a pH of 6 or higher need not be limed. FERTILIZER: Soil test results are used to determine if and when fertilizers are needed. If fertilizers are needed, apply a 10-10-10 lb/acre fertilizer at 700-1,000 lb/acre. Both fertilizer and lime should be incorporated into the top 4-6 inches of soil. If a hydraulic seeder is used, do not mix seed and fertilizer more than 30 minutes before application. SURFACE ROUGHENING: If recent tillage operations have resulted in a loose surface additional roughening may not be required, except to break up large clods. If rainfall causes the surface to become sealed or crusted, loosen it just prior to seeding by tilling, harrowing, or other suitable methods for fine grading. The finished grade should be a smooth even soil surface with a loosen uniformly fine texture. All ridges and depressions shall be removed and filled to provide the approved surface drainage. Planting is to be done immediately after finished grades are obtained and seedbed preparation is completed.																														
NOTES:																														
1. Permanent seeding, sodding or other means of stabilization are required when all construction work is completed according to the NPDES stormwater table. 2. Seeding, sodding or other means of stabilization are required for all areas to be seeded, sodded or planted. 3. Use a seeding mix that will produce fast-growing nurse crops and includes non-invasive species that will eventually provide a permanent groundcover. Soil blankets may be used in lieu of nurse crops. 4. Mat, tack or crimp mulch, as needed to stabilize seeded areas until root establishment. Mulch must cover at least 80% of the soil surface. 5. Ground cover shall be maintained until permanent vegetation is established and stable against accelerated erosion.																														



PERMANENT SEEDING

Effective Date: 9/1/2023
 In accordance with the 2013
 Design Manual Updates

The diagram illustrates a temporary gravel construction entrance/exit. It shows a gravel pad (2-3" course aggregate) sloping away from a 'Public Road' (indicated by a dashed line). The pad has a minimum width of 6' and a minimum length of 50' (or 50' MIN. SUFFICIENT ENOUGH TO RETAIN SEDIMENT ON SITE AND OFF ROADWAYS). The pad is bordered by geotextile fabric (6" MIN. thick) in locations subject to seepage or high water table. The pad is bordered by a 12' MIN. wide area (AS REQUIRED) on the right side. The pad is bordered by a 12' MIN. wide area (AS REQUIRED) on the right side.

Construction:

1. Clear the entrance and exit area of all vegetation, roots, and other objectionable material and properly grade it.
2. Place the gravel to the specific grade and dimensions shown on the plans, and smooth it.
3. Provide drainage to carry water to a sediment trap or other suitable outlet.
4. Use geotextile fabrics in order to improve stability of the foundation in locations subject to seepage or high water table.

Maintenance:

1. Inspect all measures at least weekly and after each rainfall of 1.0 inch or greater. Make any required repairs immediately.
2. Maintain the gravel pad in a condition to prevent mud or sediment from leaving the construction site. This may require periodic topdressing with 2-inch stone.
3. Sediment on roadways is to be removed immediately by broom and shovel, either by manual or mechanical means, and not to be washed off where it has the potential to enter a stream, drainage way or storm drain system.

DATE: _____

8" MAX. STANDARD TENSILE FABRIC WITH WIRE FENCE
6" MAX. EXTRA STRENGTH FABRIC WITHOUT WIRE FENCE

STEEL POST

WIRE FENCE

18-24"

8" DOWN & 4" FORWARD ALONG THE TRENCH

24"

PLASTIC OR WIRE TIES

24"

WIRE FENCE

PLASTIC OR WIRE

STEEL POST

24"

4" MIN.

8" MIN.

UP-SLOPE

CROSS SECTION VIEW

Notes:

- Construct the sediment barrier of standard strength or extra strength synthetic filter fabrics.
- Ensure that the height of the sediment fence does not exceed 24 inches above the ground. (Higher fences may impound volumes of water sufficient to cause failure of the structure)
- Construct the filter fabric from a continuous roll cut to the length of the barrier to avoid joints. When joints are necessary, securely fasten the filter cloth only at a support post with 4 feet minimum overlap to the next post.
- Support standard strength filter fabric by wire mesh fastened securely to the upslope side of the posts. Extend the wire mesh support to the bottom of the trench. Fasten the wire reinforcement, then fabric on the upslope side of the fence post. Wire or plastic zip ties should have a minimum 50 pound tensile strength.
- When a wire mesh support fence is used, space posts a maximum of 8 feet apart. Supports should be driven securely into the ground a minimum of 24 inches. Wire mesh should be a minimum 14-gauge with 6 inch mesh spacing.
- Extra strength filter fabric with 6 foot post spacing does not require a wire mesh support fence. Securely fasten the filter fabric directly to posts. Wire or plastic zip ties should have a minimum of 50 pound tensile strength.
- Excavate the trench approximately 4 inches wide and 8 inches deep along the proposed line of the posts and upslope from the barrier.
- Place 12 inches of fabric along the bottom and side of the trench.
- Backfill the trench with soil placed over the filter fabric and compact. Thorough compaction of the backfill is critical to silt fence performance.
- Do not attach filter fabric to existing trees.
- Do not place across ditches, streams, or any other areas of concentrated flow.

Max. Slope Length and Slope for Which Sediment Fence is Applicable

Slope	Slope Length (ft)	Max. Area (ft ²)
<2%	100	10,000
2 to 5%	75	7,500
5 to 10%	50	5,000
10 to 20%	25	2,500
>20%	15	1,500

Maintenance:

- Inspect all measures at least weekly and after each rainfall of 1.0 inch or greater. Make any required repairs immediately.
- Should the fabric of a sediment fence collapse, tear, decompose, or become ineffective, replace it promptly.
- Remove sediment deposits as necessary to provide adequate storage volume for the next rain and reduce pressure on the fence. Take care to avoid undermining the fence during cleanouts.
- Remove all fencing materials and unstable sediment deposits and bring the area to grade and stabilize it after the contributing drainage area has been properly stabilized.



Rochester
Engineering, Inc.

Rochester Engineering, INC.
425 Oak St NW, Gainesville, GA 30501
770.718.0600 | rochester.dccm.com

GROUND STABILIZATION AND MATERIALS HANDLING PRACTICES FOR COMPLIANCE WITH THE NCG01 CONSTRUCTION GENERAL PERMIT

Implementing the details and specifications on this plan sheet will result in the construction activity being considered compliant with the Ground Stabilization and Materials Handling sections of the NCG01 Construction General Permit (Sections E and F, respectively). The permittee shall comply with the Erosion and Sediment Control plan approved by the delegated authority having jurisdiction. All details and specifications shown on this sheet may not apply depending on site conditions and the delegated authority having jurisdiction.

SECTION E: GROUND STABILIZATION

Required Ground Stabilization Timeframes		
Site Area Description	Stabilize within this many calendar days after ceasing land disturbance	Timeframe variations
(a) Perimeter dikes, swales, ditches, and perimeter slopes	7	None
(b) High Quality Water (HQW) Zones	7	None
(c) Slopes steeper than 3:1	7	If slopes are 10' or less in length and are not steeper than 2:1, 14 days are allowed
(d) Slopes 3:1 to 4:1	14	-7 days for slopes greater than 50' in length and with slopes steeper than 4:1 -7 days for perimeter dikes, swales, ditches, perimeter slopes and HQW Zones -10 days for Falls Lake Watershed
(e) Areas with slopes flatter than 4:1	14	-7 days for perimeter dikes, swales, ditches, perimeter slopes and HQW Zones -10 days for Falls Lake Watershed unless there is zero slope

Note: After the permanent cessation of construction activities, any areas with temporary ground stabilization shall be converted to permanent ground stabilization as soon as practicable but in no case longer than 90 calendar days after the last land disturbing activity. Temporary ground stabilization shall be maintained in a manner to render the surface stable against accelerated erosion until permanent ground stabilization is achieved.

GROUND STABILIZATION SPECIFICATION

Stabilize the ground sufficiently so that rain will not dislodge the soil. Use one of the techniques in the table below:

Temporary Stabilization	Permanent Stabilization
<ul style="list-style-type: none">Temporary grass seed covered with straw or other mulches and tackifiersHydroseedingRolls of erosion control products with or without temporary grass seedAppropriately applied straw or other mulchPlastic sheeting	<ul style="list-style-type: none">Permanent grass seed covered with straw or other mulches and tackifiersGeotextile fabrics such as permanent soil reinforcement mattingHydroseedingShrubs or other permanent plantings covered with mulchUniform and evenly distributed ground cover sufficient to restrain erosionStructural methods such as concrete, asphalt or retaining wallsRolls of erosion control products with grass seed

POLYACRYLAMIDES (PAMS) AND FLOCCULANTS

- Select flocculants that are appropriate for the soils being exposed during construction, selecting from the *NC DWR List of Approved PAMS/Flocculants*.
- Apply flocculants at or before the inlets to Erosion and Sediment Control Measures.
- Apply flocculants at the concentrations specified in the *NC DWR List of Approved PAMS/Flocculants* and in accordance with the manufacturer's instructions.
- Provide ponding area for containment of treated Stormwater before discharging offsite.
- Store flocculants in leak-proof containers that are kept under storm-resistant cover or surrounded by secondary containment structures.

EQUIPMENT AND VEHICLE MAINTENANCE

- Maintain vehicles and equipment to prevent discharge of fluids.
- Provide drip pans under any stored equipment.
- Identify leaks and repair as soon as feasible, or remove leaking equipment from the project.
- Collect all spent fluids, store in separate containers and properly dispose as hazardous waste (recycle when possible).
- Remove leaking vehicles and construction equipment from service until the problem has been corrected.
- Bring used fuels, lubricants, coolants, hydraulic fluids and other petroleum products to a recycling or disposal center that handles these materials.

LITTER, BUILDING MATERIAL AND LAND CLEARING WASTE

- Never bury or burn waste. Place litter and debris in approved waste containers.
- Provide a sufficient number and size of waste containers (e.g. dumpster, trash receptacle) on site to contain construction and domestic wastes.
- Locate waste containers at least 50 feet away from storm drain inlets and surface waters unless no other alternatives are reasonably available.
- Locate waste containers on areas that do not receive substantial amounts of runoff from upland areas and does not drain directly to a storm drain, stream or wetland.
- Cover waste containers at the end of each workday and before storm events or provide secondary containment. Repair or replace damaged waste containers.
- Anchor all lightweight items in waste containers during times of high winds.
- Empty waste containers as needed to prevent overflow. Clean up immediately if containers overflow.
- Dispose waste off-site at an approved disposal facility.
- On business days, clean up and dispose of waste in designated waste containers.

PAINT AND OTHER LIQUID WASTE


- Do not dump paint and other liquid waste into storm drains, streams or wetlands.
- Locate paint washouts at least 50 feet away from storm drain inlets and surface waters unless no other alternatives are reasonably available.
- Contain liquid wastes in a controlled area.
- Containment must be labeled, sized and placed appropriately for the needs of site.
- Prevent the discharge of soaps, solvents, detergents and other liquid wastes from construction sites.

PORTABLE TOILETS

- Install portable toilets on level ground, at least 50 feet away from storm drains, streams or wetlands unless there is no alternative reasonably available. If 50 foot offset is not attainable, provide relocation of portable toilet behind silt fence or place on a gravel pad and surround with sand bags.
- Provide staking or anchoring of portable toilets during periods of high winds or in high foot traffic areas.
- Monitor portable toilets for leaking and properly dispose of any leaked material. Utilize a licensed sanitary waste hauler to remove leaking portable toilets and replace with properly operating unit.

EARTHEN STOCKPILE MANAGEMENT

- Show stockpile locations on plans. Locate earthen-material stockpile areas at least 50 feet away from storm drain inlets, sediment basins, perimeter sediment controls and surface waters unless it can be shown no other alternatives are reasonably available.
- Protect stockpile with silt fence installed along toe of slope with a minimum offset of five feet from the toe of stockpile.
- Provide stable stone access point when feasible.
- Stabilize stockpile within the timeframes provided on this sheet and in accordance with the approved plan and any additional requirements. Soil stabilization is defined as vegetative, physical or chemical coverage techniques that will restrain accelerated erosion on disturbed soils for temporary or permanent control needs.



CONCRETE WASHOUTS

- Do not discharge concrete or cement slurry from the site.
- Dispose of, or recycle settled, hardened concrete residue in accordance with local and state solid waste regulations and at an approved facility.
- Manage washout from mortar mixers in accordance with the above item and in addition place the mixer and associated materials on impervious barrier and within lot perimeter silt fence.
- Install temporary concrete washouts per local requirements, where applicable. If an alternate method or product is to be used, contact your approval authority for review and approval. If local standard details are not available, use one of the two types of temporary concrete washouts provided on this detail.
- Do not use concrete washouts for dewatering or storing defective curb or sidewalk sections. Stormwater accumulated within the washout may not be pumped into or discharged to the storm drain system or receiving surface waters. Liquid waste must be pumped out and removed from project.
- Locate washouts at least 50 feet from storm drain inlets and surface waters unless it can be shown that no other alternatives are reasonably available. At a minimum, install protection of storm drain inlet(s) closest to the washout which could receive spills or overflow.
- Locate washouts in an easily accessible area, on level ground and install a stone entrance pad in front of the washout. Additional controls may be required by the approving authority.
- Install at least one sign directing concrete trucks to the washout within the project limits. Post signage on the washout itself to identify this location.
- Remove leavings from the washout when at approximately 75% capacity to limit overflow events. Replace the tarp, sand bags or other temporary structural components when no longer functional. When utilizing alternative or proprietary products, follow manufacturer's instructions.
- At the completion of the concrete work, remove remaining leavings and dispose of in an approved disposal facility. Fill pit, if applicable, and stabilize any disturbance caused by removal of washout.


HERBICIDES, PESTICIDES AND RODENTICIDES

- Store and apply herbicides, pesticides and rodenticides in accordance with label restrictions.
- Store herbicides, pesticides and rodenticides in their original containers with the label, which lists directions for use, ingredients and first aid steps in case of accidental poisoning.
- Do not store herbicides, pesticides and rodenticides in areas where flooding is possible or where they may spill or leak into wells, stormwater drains, ground water or surface water. If a spill occurs, clean area immediately.
- Do not stockpile these materials onsite.

HAZARDOUS AND TOXIC WASTE

- Create designated hazardous waste collection areas on-site.
- Place hazardous waste containers under cover or in secondary containment.
- Do not store hazardous chemicals, drums or bagged materials directly on the ground.

**TURBIDITY CURTAIN SYSTEM
ANCHOR SYSTEM AND LAYOUT DETAILS**



NCG01 GROUND STABILIZATION AND MATERIALS HANDLING

EFFECTIVE: 04/01/19



Rochester Engineering, Inc.
425 Oak St NW, Gainesville, GA 30501
770.718.0600 | rochester.dccm.com

**EROSION CONTROL DETAILS
FOR:
STONE BRIDGE**

LOCATED IN:
HAWASSEE TOWNSHIP
CLAY COUNTY, NORTH CAROLINA

**PART III
SELF-INSPECTION, RECORDKEEPING AND REPORTING**

SECTION A: SELF-INSPECTION

Self-inspections are required during normal business hours in accordance with the table below. When adverse weather or site conditions would cause the safety of the inspection personnel to be in jeopardy, the inspection may be delayed until the next business day on which it is safe to perform the inspection. In addition, when a storm event of equal to or greater than 1.0 inch occurs outside of normal business hours, the self-inspection shall be performed upon the commencement of the next business day. Any time when inspections were delayed shall be noted in the Inspection Record.

Inspect	Frequency (during normal business hours)	Inspection records must include:
(1) Rain gauge maintained in good working order	Daily	Daily rainfall amounts. If no daily rain gauge observations are made during weekend or holiday periods, and no individual day rainfall information is available, record the cumulative rain measurement for those unattended days (and this will determine if a site inspection is needed). Days on which no rainfall occurred shall be recorded as "zero." The permittee may use another rain-measuring device approved by the Division.
(2) E&SC Measures	At least once per 7 calendar days and within 24 hours of a rain event ≥ 1.0 inch in 24 hours	1. Identification of the measures inspected. 2. Date and time of the inspection. 3. Name of the person performing the inspection. 4. Indication of whether the measures were operating properly. 5. Description of maintenance needs for the measure. 6. Description, evidence, and date of corrective actions taken.
(3) Stormwater discharge outfalls (SDCO)	At least once per 7 calendar days and within 24 hours of a rain event ≥ 1.0 inch in 24 hours	1. Identification of the discharge outfalls inspected. 2. Date and time of the inspection. 3. Name of the person performing the inspection. 4. Evidence of indicators of stormwater pollution such as oil sheen, floating or suspended solids or discoloration. 5. Indication of visible sediment leaving the site. 6. Description, evidence, and date of corrective actions taken.
(4) Perimeter of site	At least once per 7 calendar days and within 24 hours of a rain event ≥ 1.0 inch in 24 hours	If visible sedimentation is found outside site limits, then a record of the following shall be made: 1. Actions taken to clean up or stabilize the sediment that has left the site limits. 2. Description, evidence, and date of corrective actions taken, and 3. An explanation as to the actions taken to control future releases.
(5) Streams or wetlands onsite or offsite (where accessible)	At least once per 7 calendar days and within 24 hours of a rain event ≥ 1.0 inch in 24 hours	If the stream or wetland has increased visible sedimentation or a stream has visible increased turbidity from the construction activity, then a record of the following shall be made: 1. Description, evidence and date of corrective actions taken, and 2. Records of the required reports to the appropriate Division Regional Office per Part III, Section C, Item (2)(c) of this permit.
(6) Ground stabilization measures	After each phase of grading	1. The phase of grading (installation of perimeter E&SC measures, clearing and grubbing, installation of storm drainage facilities, completion of all land-disturbing activity, construction or redevelopment, permanent ground cover). 2. Documentation that the required ground stabilization measures have been provided within the required timeframe or an assurance that they will be provided as soon as possible.

NOTE: The rain inspection resets the required 7 calendar day inspection requirement.

**PART II, SECTION 6, ITEM (4)
DRAW DOWN OF SEDIMENT BASINS FOR MAINTENANCE OR CLOSE OUT**

Sediment basins and traps that receive runoff from drainage areas of one acre or more shall use outlet structures that withdraw water from the surface when these devices need to be drawn down for maintenance or close out unless this is infeasible. The circumstances in which it is not feasible to withdraw water from the surface shall be rare (for example, times with extended cold weather). Non-surface withdrawals from sediment basins shall be allowed only when all of the following criteria have been met:

- The E&SC plan authority has been provided with documentation of the non-surface withdrawal and the specific time periods or conditions in which it will occur. The non-surface withdrawal shall not commence until the E&SC plan authority has approved these items.
- The non-surface withdrawal has been reported as an anticipated bypass in accordance with Part III, Section C, Item (2)(c) and (d) of this permit.
- Dewatering discharges are treated with controls to minimize discharges of pollutants from stormwater that is removed from the sediment basin. Examples of appropriate controls include properly sited, designed and maintained dewatering tanks, weir tanks, and filtration systems.
- Vegetated, upland areas of the sites or a properly designed stone pad is used to the extent feasible at the outlet of the dewatering treatment devices described in Item (c) above.
- Velocity dissipation devices such as check dams, sediment traps, and riprap are provided at the discharge points of all dewatering devices, and
- Sediment removed from the dewatering treatment devices described in Item (c) above is disposed of in a manner that does not cause deposition of sediment into waters of the United States.

**PART III
SELF-INSPECTION, RECORDKEEPING AND REPORTING**

SECTION B: RECORDKEEPING

1. E&SC Plan Documentation

The approved E&SC plan as well as any approved deviation shall be kept on the site. The approved E&SC plan must be kept up-to-date throughout the coverage under this permit. The following items pertaining to the E&SC plan shall be kept on site and available for inspection at all times during normal business hours.

Item to Document	Documentation Requirements
(a) Each E&SC measure has been installed and does not significantly deviate from the locations, dimensions and relative elevations shown on the approved E&SC plan.	Initial and date each E&SC measure on a copy of the approved E&SC plan or complete, date and sign an inspection report that lists each E&SC measure shown on the approved E&SC plan. This documentation is required upon the initial installation of the E&SC measures or if the E&SC measures are modified after initial installation.
(b) A phase of grading has been completed.	Initial and date a copy of the approved E&SC plan or complete, date and sign an inspection report to indicate completion of the construction phase.
(c) Ground cover is located and installed in accordance with the approved E&SC plan.	Initial and date a copy of the approved E&SC plan or complete, date and sign an inspection report to indicate compliance with approved ground cover specifications.
(d) The maintenance and repair requirements for all E&SC measures have been performed.	Complete, date and sign an inspection report.
(e) Corrective actions have been taken to E&SC measures.	Initial and date a copy of the approved E&SC plan or complete, date and sign an inspection report to indicate the completion of the corrective action.

2. Additional Documentation to be Kept on Site

In addition to the E&SC plan documents above, the following items shall be kept on the site and available for inspectors at all times during normal business hours, unless the Division provides a site-specific exemption based on unique site conditions that make this requirement not practical:

- This General Permit as well as the Certificate of Coverage, after it is received.
- Records of inspections made during the previous twelve months. The permittee shall record the required observations on the Inspection Record Form provided by the Division or a similar inspection form that includes all the required elements. Use of electronically-available records in lieu of the required paper copies will be allowed if shown to provide equal access and utility as the hard-copy records.

3. Documentation to be Retained for Three Years

All data used to complete the e-NOI and all inspection records shall be maintained for a period of three years after project completion and made available upon request. [40 CFR 122.41]



Table 6.10a Temporary Seeding Recommendations for Late Winter and Early Spring	
Seeding mixture Species	Rate (lb/acre)
Rye (grain) Annual lespedeza (Kobe in Piedmont and Coastal Plain, Korean in Mountains)	120 50
Omit annual lespedeza when duration of temporary cover is not to extend beyond June.	
Seeding dates Mountains—Above 2500 feet: Feb. 15 - May 15 Below 2500 feet: Feb. 1 - May 1 Piedmont—Jan. 1 - May 1 Coastal Plain—Dec. 1 - Apr. 15	
Soil amendments Follow recommendations of soil tests or apply 2,000 lb/acre ground agricultural limestone and 750 lb/acre 10-10-10 fertilizer.	
Mulch Apply 4,000 lb/acre straw. Anchor straw by tacking with asphalt, netting, or a mulch anchoring tool. A disk with blades set nearly straight can be used as a mulch anchoring tool.	
Maintenance Referfertilize if growth is not fully adequate. Reseed, referfertilize and mulch immediately following erosion or other damage.	

ANY CHANGES OR ALTERATIONS MADE TO THIS PLAN SHEET SHALL BE THE RESPONSIBILITY OF THE PERMITTEE. IT IS THE WRITTEN APPROVAL OF ROCHESTER ENGINEERING, INC. THAT THE SEAL SHOWN HEREON AND THE SIGNATURE OF THE PERMITTEE'S DESIGNATED REPRESENTATIVE ON THE ORIGINAL DRAWINGS ARE KEPT ON FILE FOR VERIFICATION OF ANY CHANGES.

1ST SUBMITTAL


SHEET
28
OF
31

DATE: 04/28/25
SCALE: N.T.S.
JOB NO.: 25-0000-THM
DRAWN BY: CWS
CHECKED BY: CWS
DESIGNED BY: CWS

NCG01 SELF-INSPECTION, RECORDKEEPING AND REPORTING

EFFECTIVE: 04/01/19

6.10.4




LOC.	PIPE DIA.	SINGLE PIPE										DOUBLE PIPE									
		16"	18"	24"	30"	36"	42"	48"	54"	60"	66"	16"	18"	24"	30"	36"	42"	48"	54"	60"	66"
BARS	"X"	"X"	"X"	"X"	"X"	"X"	"X"	"X"	"X"	"X"	"X"	"X"	"X"	"X"	"X"	"X"	"X"	"X"	"X"	"X"	"X"
G QTY.		2	2	3	3	4	4	4	5	5	6	2	2	3	3	4	4	4	5	5	6
M QTY.		-	-	-	-	-	-	2	-	2	1	1	1	2	2	2	2	2	3	3	2
G QTY.		2	2	3	3	4	4	5	5	6	2	2	3	3	4	4	4	5	5	6	6
TOTAL LBS.		9	9	14	14	19	19	55	55	62	12	12	19	19	23	23	77	77	92	92	92

USING CONCRETE PIPE											
COMMON DIMENSIONS				SINGLE PIPE				DOUBLE PIPE			
D	H	B	G	T	S	L	VD ³	M	L	VD ³	
16"	3'-3"	1'-8"	2'-0"	2'-4"	9 1/2"	5'-6"	0.7	2'-2"	7'-8"	1.0	
18"	3'-7"	1'-10"	2'-2"	2'-6"	10"	6'-4"	1.0	2'-7"	8'-11"	1.3	
24"	4'-2"	2'-11"	4'-0"	3"	10"	8'-0"	1.5	3'-5"	11'-5"	2.0	
30"	5'-0"	2'-6"	4'-7"	4 1/4"	11 1/2"	9'-2"	2.3	4'-3"	13'-5"	3.1	
36"	5'-8"	2'-8"	5'-6"	4 3/4"	11 1/2"	11'-0"	3.4	5'-0"	16'-0"	4.6	
42"	6'-2"	3'-11"	6'-4"	5 1/4"	11 1/2"	12'-8"	4.5	5'-10"	18'-8"	6.0	
48"	6'-8"	3'-5"	7'-2"	5 3/4"	11 1/2"	14'-4"	6.0	6'-8"	21'-0"	8.0	

STATE OF NORTH CAROLINA
DEPT. OF TRANSPORTATION
DIVISION OF HIGHWAYS
RALEIGH, N.C.

ROADWAY STANDARD DRAWING FOR
CONCRETE ENDWALL FOR SINGLE
AND DOUBLE PIPE CULVERTS
15' THRU 48" PIPE - 90° SKEN

SHEET 1 OF 3
838.01



LOC.	PIPE DIA.	SINGLE PIPE										DOUBLE PIPE									
		16"	18"	24"	30"	36"	42"	48"	54"	60"	66"	16"	18"	24"	30"	36"	42"	48"	54"	60"	66"
BARS	"X"	"X"	"X"	"X"	"X"	"X"	"X"	"X"	"X"	"X"	"X"	"X"	"X"	"X"	"X"	"X"	"X"	"X"	"X"	"X"	"X"
G QTY.		2	2	3	3	4	4	5	5	6	6	2	2	3	3	4	4	4	5	5	6
M QTY.		-	-	-	-	-	-	2	-	2	1	1	1	2	2	2	2	2	3	3	2
G QTY.		2	2	3	3	4	4	5	5	6	2	2	3	3	4	4	4	5	5	6	6
TOTAL LBS.		9	9	14	14	19	19	55	55	62	12	12	19	19	23	23	73	73	80	80	80

USING CORRUGATED STEEL PIPE											
COMMON				SINGLE PIPE				DOUBLE PIPE			
D	H	B	G	T	S	L	VD ³	M	L	VD ³	
16"	3'-4"	1'-8"	2'-6"	2'-0"	0.7	1'-11"	6'-11"	1.0			
18"	3'-7"	1'-10"	2'-11"	5'-10"	1.0	2'-3"	8'-1"	1.2			
24"	4'-1"	2'-1"	3'-8"	7'-4"	1.4	3'-0"	10'-4"	1.8			
30"	4'-7"	2'-4"	4'-5"	8'-10"	2.0	3'-9"	12'-7"	2.7			
36"	5'-1"	2'-7"	5'-2"	10'-4"	2.8	4'-8"	14'-10"	3.8			
42"	5'-7"	2'-10"	5'-11"	11'-10"	3.8	5'-3"	17'-1"	5.0			
48"	6'-1"	3'-1"	6'-8"	13'-4"	4.9	6'-0"	19'-4"	7.5			

STATE OF NORTH CAROLINA
DEPT. OF TRANSPORTATION
DIVISION OF HIGHWAYS
RALEIGH, N.C.

ROADWAY STANDARD DRAWING FOR
CONCRETE ENDWALL FOR SINGLE
AND DOUBLE PIPE CULVERTS
15' THRU 48" PIPE - 90° SKEN

SHEET 2 OF 3
838.01

GENERAL NOTES:

CHAMFER ALL CORNERS 1" OR HAVE A RADIUS OF 1".

PLACE 2 #6 "Y" BARS IN THE TOP OF ALL ENDWALL FOR PIPE CULVERTS 42" AND OVER WITH A MINIMUM OF 3" COVER AND A LENGTH OF 6" LESS THAN ENDWALL LENGTH.

CONSTRUCT BOTTOM SLAB WITH FORMS.

DO NOT INTERPRET WALL THICKNESS (T) SHOWN FOR THE THICKNESS ACCEPTABLE, BUT IS USED IN COMPUTING ENDWALL QUANTITIES.

WHEN THE CONTRACTOR ELECTS TO USE A CONSTRUCTION JOINT AT THE BOTTOM OF THE PIPE, PLACE BAR "X" DOWELS IN THE BASE AS SHOWN ON PLANS. SPACE BARS APPROXIMATELY ON 12" CENTERS UNLESS OTHERWISE DIRECTED BY THE ENGINEER.


WHEN THE CONTRACTOR ELECTS TO USE A CONSTRUCTION JOINT AT THE BOTTOM OF THE PIPE AND POUR THE BASE SEPARATELY LEAVE THE POUR ROUGH.

USE CLASS "B" CONCRETE.

STATE OF NORTH CAROLINA
DEPT. OF TRANSPORTATION
DIVISION OF HIGHWAYS
RALEIGH, N.C.

ROADWAY STANDARD DRAWING FOR
CONCRETE ENDWALL FOR SINGLE
AND DOUBLE PIPE CULVERTS
15' THRU 48" PIPE - 90° SKEN


SHEET 3 OF 3
838.01



STATE OF NORTH CAROLINA
DEPT. OF TRANSPORTATION
DIVISION OF HIGHWAYS
RALEIGH, N.C.

ROADWAY STANDARD DRAWING FOR
CONCRETE CATCH BASIN
12" THRU 54" PIPE

SHEET 1 OF 2
840.02




MINIMUM DIMENSIONS AND QUANTITIES FOR CONCRETE CATCH BASIN (BASED ON MIN. HEIGHT, H, WITH NO RISER) *											
DIMENSIONS OF BOX AND PIPE				COVER DIMENSION				BARS			
PIPE DIA.	SPAN	WIDTH	DEPTH	C	E	F	G	NO. LENGTH	NO. WIDTH	NO. DEPTH	TOTAL
12"	3'-0"	2'-2"	2'-0"	2'-8"	2'-0"	2'-0"	2'-0"	3	3	3	9
15"	3'-0"	2'-2"	2'-0"	3'-0"	2'-0"	2'-0"	2'-0"	3	3	3	9
18"	3'-0"	2'-2"	2'-0"	3'-0"	2'-0"	2'-0"	2'-0"	3	3	3	9
24"	3'-0"	2'-2"	2'-0"	3'-0"	2'-0"	2'-0"	2'-0"	3	3	3	9
30"	3'-0"	2'-2"	2'-0"	3'-0"	2'-0"	2'-0"	2'-0"	3	3	3	9
36"	3'-0"	2'-2"	2'-0"	3'-0"	2'-0"	2'-0"	2'-0"	3	3	3	9
42"	3'-0"	2'-2"	2'-0"	3'-0"	2'-0"	2'-0"	2'-0"	3	3	3	9
48"	3'-0"	2'-2"	2'-0"	3'-0"	2'-0"	2'-0"	2'-0"	3	3	3	9
54"	3'-0"	2'-2"	2'-0"	3'-0"	2'-0"	2'-0"	2'-0"	3	3	3	9

STATE OF NORTH CAROLINA
DEPT. OF TRANSPORTATION
DIVISION OF HIGHWAYS
RALEIGH, N.C.

ROADWAY STANDARD DRAWING FOR
CONCRETE CATCH BASIN
12" THRU 54" PIPE

SHEET 2 OF 2
840.02



STATE OF NORTH CAROLINA
DEPT. OF TRANSPORTATION
DIVISION OF HIGHWAYS
RALEIGH, N.C.

ROADWAY STANDARD DRAWING FOR
FRAME, GRATES, AND HOOD
FOR USE ON STANDARD CATCH BASIN

SHEET 1 OF 2
840.03

Rochester Engineering, Inc.
Rochester Engineering, Inc.
425 Oak St NW, Gainesville, GA 30501
770.718.0600 | rochester.dccm.com

FOR:
STONE BRIDGE
CONSTRUCTION DETAILS










LOCATED IN:
HAMASSEE TOWNSHIP
CLAY COUNTY, NORTH CAROLINA

ANY CHANGES OR ALTERATIONS MADE TO THIS DRAWING SHALL BE THE RESPONSIBILITY OF THE USER. THE USER SHALL BE RESPONSIBLE FOR OBTAINING THE WRITTEN APPROVAL OF ROCHESTER ENGINEERING, INC. BEFORE ANY CHANGES ARE MADE TO THIS DRAWING. ORIGINAL DRAWINGS ARE KEPT ON FILE FOR VERIFICATION OF ANY CHANGES.

1ST SUBMITTAL

SHEET
30
OF
31

DATE: 04/28/25
SCALE: N.T.S.
JOB NO.: 25055 TMM
DRAWN BY: C.M.S.
CHECKED BY: C.M.S.



**JOINT APPLICATION FOR
STONE BRIDGE RESIDENTIAL / MARINA PROJECT
CLAY COUNTY, NORTH CAROLINA**

ATTACHMENTS

ATTACHMENT 1 – STONE BRIDGE RESIDENTIAL / MARINA PROJECT MAP SET

ATTACHMENT 2 – PROJECT DESCRIPTION, ALTERNATIVES ANALYSIS, AVOIDANCE & MINIMIZATION

ATTACHMENT 3 – USACE FORM 4345

ATTACHMENT 4 – STONE BRIDGE RESIDENTIAL DEVELOPMENT ENGINEERING PLANS

ATTACHMENT 5 – STONE BRIDGE MARINA COVE DEEPENING ENGINEERING PLANS

ATTACHMENT 6 – IPAC SPECIES LIST

ATTACHMENT 7 – STONE BRIDGE DELINEATION REPORT

ATTACHMENT 8 – ADJACENT PROPERTY OWNERS

LOCATED IN
HIAWASSEE TOWNSHIP
CLAY COUNTY, NORTH CAROLINA

**PROPOSED DEVELOPMENT BY:
BROWN HAVEN HOMES**



Rochester
Engineering, Inc.


OWNER & DEVELOPER:
BROWN HAVEN HOMES
837 HWY 400
SUITE 105
DAWSONVILLE, GA 30534
(706) 970-2456
john@brownhavenhomes.com

24 HOUR CONTACT:

 JOHN ALLEN
 (706) 970-2456
john@brownhavenhomes.com

The logo for NC 811.ORG features the text "NC 811.ORG" in a bold, green, sans-serif font with a black outline. Below the text is a stylized graphic of a shovel with a grey head and a brown handle, positioned as if digging into the ground.

1ST SUBMITTAL



**TAX PARCEL ID: 548901284729, 548901293357,
548901292054, & 548901199661
G224096.TNM
01/08/25**

No.	Date	DESCRIPTIONS REVISIONS

Sheet List Table	
Sheet Number	Sheet Title
1	COVER SHEET
2	GENERAL NOTES
3	EXISTING SITE PLAN
4	EROSION CONTROL PLAN
5	EROSION CONTROL DETAILS
6	EROSION CONTROL DETAILS

GENERAL SITE NOTES:

1. "PRIOR TO STARTING CONSTRUCTION CONTRACTOR SHALL BE RESPONSIBLE TO MAKE SURE THAT ALL REQUIRED PERMITS AND APPROVALS HAVE BEEN OBTAINED. NO CONSTRUCTION OR FABRICATION SHALL BEGIN UNTIL THE CONTRACTOR HAS RECEIVED AND THOROUGHLY REVIEWED ALL PLANS AND OTHER DOCUMENTS APPROVED BY ALL OF THE PERMITTING AUTHORITIES."

2. ALL WORK SHALL BE PERFORMED IN ACCORDANCE WITH THESE PLANS AND SPECIFICATIONS AND THE REQUIREMENTS AND STANDARDS OF THE LOCAL GOVERNING AUTHORITY.

3. THE RIGHT OF WAY INFORMATION, TOPOGRAPHY, UTILITIES, AND PHYSICAL FEATURES WERE TAKEN FROM A TOPOGRAPHIC SURVEY AND BOUNDARY PLAT CONDUCTED BY ROCHESTER & ASSOCIATES, INC. FIELD DATA WAS COLLECTED IN MAY OF 2018.

4. THE LOCATIONS OF UNDERGROUND FACILITIES SHOWN ON THIS PLAN ARE BASED ON FIELD SURVEYS AND LOCAL UTILITY COMPANY RECORDS. IT SHALL BE THE CONTRACTOR'S FULL RESPONSIBILITY TO CONTACT THE VARIOUS UTILITY COMPANIES TO LOCATE THEIR FACILITIES PRIOR TO STARTING CONSTRUCTION. NO ADDITIONAL COMPENSATION SHALL BE PAID TO THE CONTRACTOR FOR DAMAGE AND REPAIR TO THESE FACILITIES CAUSED BY HIS WORK FORCE.

5. ALL DIMENSIONS AND GRADES SHOWN ON THE PLANS SHALL BE FIELD VERIFIED BY THE CONTRACTOR PRIOR TO CONSTRUCTION. CONTRACTOR SHALL NOTIFY THE OWNER'S CONSTRUCTION MANAGER IF ANY DISCREPANCIES EXIST PRIOR TO PROCEEDING WITH CONSTRUCTION FOR NECESSARY PLAN OR GRADE CHANGES. NO EXTRA COMPENSATION SHALL BE PAID TO CONTRACTOR FOR WORK HAVING TO BE REDONE DUE TO DIMENSIONS OR GRADES SHOWN INCORRECTLY ON THESE PLANS IF SUCH NOTIFICATION HAS NOT BEEN GIVEN.

6. ALL DIMENSIONS ARE TO THE BACK OF CURB UNLESS OTHERWISE NOTED.

7. ANY CHANGES OR ALTERATIONS MADE TO THESE CONSTRUCTION DRAWINGS WITHOUT THE WRITTEN APPROVAL OF ROCHESTER AND ASSOCIATES, INC. VOIDS THE SEAL SHOWN HEREON AND ANY LIABILITY ASSOCIATED WITH THIS PROJECT. THE ORIGINAL DRAWINGS ARE KEPT ON FILE FOR VERIFICATION OF ANY CHANGES.

8. ALL CONSTRUCTION SHALL CONFORM TO CURRENT APPLICABLE CLAY COUNTY STANDARDS AND SPECIFICATIONS.

9. SITE IS LOCATED IN HAWASSEE TOWNSHIP, CLAY COUNTY, NORTH CAROLINA.

10. PROPOSED USE: 3 NEW DOCKS, LAKE DREDGING, WALL, SIDEWALK & BEACH CONSTRUCTION

11. DEVELOPER: BROWN HAVEN HOMES

12. CONTRACTOR SHALL NOTIFY CLAY COUNTY 24 HOURS BEFORE THE BEGINNING OF EVERY PHASE OF CONSTRUCTION.

13. UTILITY SERVICE:

GAS

WATER

COMM.

POWER

SEWER

14. 24 HOUR CONTACT: JOHN ALLEN
MOBILE: (706) 970-2456 EMAIL: JOHN@BROWNHAVENHOMES.COM

15. ENGINEERING CONTACT: JEREMY FRYDRYCH, PE, (678) 450-5203

16. PORTIONS OF THIS PROPERTY ARE LOCATED IN A FLOOD HAZARD ZONE "AE" AS PER F.E.M.A. INSURANCE RATE MAP OF CLAY COUNTY, NORTH CAROLINA. COMMUNITY PANEL NO. 3700548900J EFFECTIVE DATE NOVEMBER 19, 2008.

17. THERE ARE STREAMS AND WETLANDS ON OR WITHIN 200' OF THE PROJECT SITE.

18. THERE ARE NO STREAMS REQUIRING STATE OR LOCAL BUFFERS ON OR WITHIN 200' OF THE PROJECT SITE.

19. THIS SITE DOES NOT CONTAIN ANY KNOWN CEMETERIES.

20. ALL RETAINING WALLS WILL BE PERMITTED SEPARATELY.

21. ALL LIGHTING WILL BE LOW LEVEL AND NON-SPILL.

22. ALL PLANT MATERIAL CONFORMING TO AMERICAN STANDARD FOR NURSERY STOCK.

EROSION CONTROL NOTES:

1. DESCRIPTION: 3 NEW DOCKS, LAKE DREDGING, WALL, SIDEWALK & BEACH CONSTRUCTION

2. EXISTING CONDITIONS: OPEN GRASSED FIELDS & WETLANDS

3. ADJACENT AREAS: THE SITE IS BOUNDED TO THE NORTH & EAST BY OFFICE, SOUTH BY A CHURCH, TO THE WEST BY A POWER SUB-STATION.

4. SOIL CLEAN UP AND CONTROL PRACTICES:

(A) LOCAL, STATE AND MANUFACTURER'S RECOMMENDED METHODS FOR SPILL CLEANUP WILL BE CLEARLY POSTED AND PROCEDURES WILL BE MADE AVAILABLE TO SITE PERSONNEL.

(B) MATERIAL AND EQUIPMENT NECESSARY FOR SPILL CLEANUP WILL BE KEPT IN THE MATERIAL STORAGE AREAS. TYPICAL MATERIAL AND EQUIPMENT INCLUDES, BUT IS NOT LIMITED TO, BROOMS, DUSTPANS, MOPS, GLOVES, GOGGLES, CAT LITTER, SAND, SAWDUST AND PROPERLY LABELED PLASTIC AND METAL WASTE CONTAINERS.

(C) SPILL PREVENTION PRACTICES AND PROCEDURES WILL BE REVIEWED AFTER A SPILL AND ADJUSTED AS NECESSARY TO FUTURE SPILLS.

(D) ALL SPILLS WILL BE CLEANED UP IMMEDIATELY UPON DISCOVERY. ALL SPILLS WILL BE REPORTED AS REQUIRED BY LOCAL, STATE AND FEDERAL REGULATIONS.

(E) FOR SPILLS THAT IMPACT SURFACE WATER (LEAVE A SHEEN ON SURFACE WATER). THE NATIONAL RESPONSE CENTER (NRC) WILL BE CONTACTED WITHIN 24 HOURS AT 1-800-426-2675.

(F) FOR SPILLS OF AN UNKNOWN AMOUNT, THE NATIONAL CENTER (NRC) WILL BE CONTACTED WITHIN 24 HOURS AT 1-800-426-2675.

(G) FOR SPILLS GREATER THAN 25 GALLONS AND NO SURFACE WATER IMPACTS, THE NORTH CAROLINA DEQ WILL BE CONTACTED WITHIN 24 HOURS.

(H) FOR SPILLS LESS THAN 25 GALLONS AND NO SURFACE WATER IMPACTS, THE SPILL WILL BE CLEANED UP AND LOCAL AGENCIES WILL BE CONTACTED AS REQUIRED.

(I) THE CONTRACTOR SHALL NOTIFY THE LICENSED PROFESSIONAL WHO PREPARED THIS PLAN IF MORE THAN 1320 GALLONS OF PETROLEUM IS STORED ONSITE (THIS INCLUDES CAPACITIES OF EQUIPMENT) OR IF ANY ONE PIECE OF EQUIPMENT HAS A CAPACITY GREATER THAN 560 GALLONS. THE CONTRACTOR WILL NEED A SPILL PREVENTION CONTAINMENT AND COUNTER MEASURES PLAN BY THAT LICENSED PROFESSIONAL.

5. INSPECTIONS & RECORD KEEPING:

a. Permittee requirements.

(1). Each day when any type of construction activity has taken place at a primary permittee's site, certified personnel provided by the primary permittee shall inspect: (a) all areas of the primary permittee's site where petroleum products are stored, used, or handled for spills and leaks from vehicles and equipment and (b) all locations at the primary permittee's site where vehicles enter or exit the site for evidence of off-site sediment tracking .. These inspections must be conducted until a Notice of Termination is submitted.

(2). Measure rainfall once every 24 hours except any non-working Saturday, non-working Sunday and non-working Federal holiday until a Notice of Termination is submitted. Measurement of rainfall may be suspended if all areas of the site have undergone final stabilization or established a crop of annual vegetation and a seeding of target perennials appropriate for the region.

(3). Certified personnel (provided by the primary permittee) shall inspect the following at least once every seven (7) calendar days and within 24 hours of the end of a storm that is 0.5 inches rainfall or greater (unless such storm ends after 5:00 PM on any Friday or on any non-working Saturday, non-working Sunday or any non-working Federal holiday in which case the inspection shall be completed by the end of the next business day and/or working day, whichever occurs first): (a) disturbed areas of the primary permittee's construction site ; (b) areas used by the primary permittee for storage of materials that are exposed to precipitation ; and (c) structural control measures. Erosion and sediment control measures identified in the Plan applicable to the primary permittee's site shall be observed to ensure that they are operating correctly. Where discharge locations or points are accessible, they shall be inspected to ascertain whether erosion control measures are effective in preventing significant impacts to receiving water(s). For areas of a site that have undergone final stabilization or established a crop of annual vegetation and a seeding of target perennials appropriate for the region, the permittee must comply with Part IV.D.4.a.(4). These inspections must be conducted until a Notice of Termination is submitted.

(4). Certified personnel (provided by the primary permittee) shall inspect at least once per month during the term of this permit (i.e., until a Notice of Termination is received by EPD) the areas of the site that have undergone final stabilization or established a crop of annual vegetation and a seeding of target perennials appropriate for the region. These areas shall be inspected for evidence of, or the potential for, pollutants entering the drainage system and the receiving water(s). Erosion and sediment control measures identified in the Plan shall be observed to ensure that they are operating correctly. Where discharge locations or points are accessible, they shall be inspected to ascertain whether erosion control measures are effective in preventing significant impacts to receiving water(s).

(5). Based on the results of each inspection, the site description and the pollution prevention and control measures identified in the Erosion, Sedimentation and Pollution Control Plan, the Plan shall be revised as appropriate not later than seven (7) calendar days following each inspection. Implementation of such changes shall be made as soon as practical but in no case later than seven (7) calendar days following each inspection.

(6). A report of each inspection that includes the name(s) of certified personnel making each inspection, the date(s) of each inspection, construction phase (i.e., initial, intermediate or final), major observations relating to the implementation of the Erosion, Sedimentation and Pollution Control Plan, and actions taken in accordance with Part IV.D.4.a.(5), of the permit shall be made and retained at the site or be readily available at a designated alternate location until the entire site or that portion of a construction project that has been phased has undergone final stabilization and a Notice of Termination is submitted to EPD. Such reports shall be readily available by end of the second business day and/or working day and shall identify all incidents of best management practices that have not been properly installed and/or maintained as described in the Plan. Where the report does not identify any incidents, the inspection report shall contain a certification that the best management practices are in compliance with the Erosion, Sedimentation and Pollution Control Plan. The report shall be signed in accordance with Part V.G.2. of this permit.

NO MATERIAL IS TO BE BURNED ON SITE. ALL WASTE MATERIAL SHALL BE DISPOSED OF AT A PERMITTED OFFSITE LANDFILL

THE INSTALLATION OF EROSION CONTROL MEASURES SHALL TAKE PLACE PRIOR TO OR CONCURRENT WITH LAND DISTURBING ACTIVITIES

ALL IMPROVEMENTS TO CONFORM WITH CLAY COUNTY CONSTRUCTION STANDARDS

NOTIFY CLAY COUNTY 24 HOURS BEFORE STARTING EACH PHASE OF CONSTRUCTION

MAXIMUM CUT OR FILL SLOPES ARE 2 HORIZONTAL TO 1 VERTICAL

ALL EROSION AND SEDIMENT CONTROL MEASURES WILL BE INSPECTED DAILY AND ANY DEFICIENCIES NOTED WILL BE CORRECTED BY THE END OF EACH DAY. ADDITIONAL EROSION CONTROL MEASURES WILL BE INSTALLED IF DEEMED NECESSARY BY ON-SITE INSPECTOR.

SITE AREA: 17.19 AC

DISTURBED AREA: 3.1 AC (INCLUDING DEDGING)

EARTHWORK ESTIMATE:

CUT: 7,000 CY

FILL: 7,000 CY WASTE

DIFFERENCE: 0 CY *

*EARTHWORK CALCULATIONS ARE BASED ON FINISHED GRADE

EARTHWORK ESTIMATE PROVIDED FOR CONVENIENCE TO CONTRACTOR ONLY. CONTRACTOR IS TO VERIFY QUANTITIES.

ADDITIONAL EROSION CONTROL NOTES:

THE DESIGN PROFESSIONAL WHO PREPARED THE ES&PC PLAN IS TO INSPECT THE INSTALLATION OF THE INITIAL SEDIMENT STORAGE REQUIREMENTS AND PERIMETER CONTROL BMPS WITHIN 7 DAYS AFTER INSTALLATION.

NON-EXEMPT ACTIVITIES SHALL NOT BE CONDUCTED WITHIN THE 25 OR 50-FOOT UNDISTURBED STREAM BUFFERS AS MEASURED FROM THE POINT OF WRESTED VEGETATION WITHOUT FIRST ACQUIRING THE NECESSARY VARIANCES AND PERMITS.

AMENDMENTS/REVISIONS TO THE ES&PC PLAN WHICH HAVE A SIGNIFICANT EFFECT ON BMPS WITH A HYDRAULIC COMPONENT MUST BE CERTIFIED BY THE DESIGN PROFESSIONAL.

WASTE MATERIALS SHALL NOT BE DISCHARGED TO WATERS OF THE STATE, EXCEPT AS AUTHORIZED BY A SECTION 404 PERMIT.

THE ESCAPE OF SEDIMENT FROM THE SITE SHALL BE PREVENTED BY THE INSTALLATION OF EROSION AND SEDIMENT CONTROL MEASURES AND PRACTICES PRIOR TO LAND DISTURBING ACTIVITIES.

EROSION CONTROL MEASURES WILL BE MAINTAINED AT ALL TIMES. IF FULL IMPLEMENTATION OF THE APPROVED PLAN DOES NOT PROVIDE FOR EFFECTIVE EROSION CONTROL, ADDITIONAL EROSION AND SEDIMENT CONTROL MEASURES SHALL BE IMPLEMENTED TO CONTROL OR TREAT THE SEDIMENT SOURCE.

ANY DISTURBED AREA LEFT EXPOSED FOR A PERIOD GREATER THAN 14 DAYS SHALL BE STABILIZED WITH MULCH OR TEMPORARY SEEDING.

DETENTION POND OR SEDIMENT BASIN / STORAGE WILL BE INSTALLED AND FUNCTIONING BEFORE ANY MAJOR GRADING OR IMPERVIOUS SURFACES ARE CONSTRUCTED.

NOTE: MAINTENANCE OF ALL EROSION CONTROL MEASURES, WHETHER TEMPORARY OR PERMANENT, SHALL AT ALL TIMES BE THE RESPONSIBILITY OF THE OWNER.

SURFACE ROUGHENING:

ALL CUT AND FILL SLOPES SHALL BE SURFACED ROUGHENED AND VEGETATED WITHIN THREE (3) DAYS AFTER GRADING.

DISPOSAL:

STUMPS AND CONSTRUCTION DEBRIS SHALL BE DEPOSITED IN A PROPERLY PERMITTED LANDFILL.

TYPE "S" SILT FENCE:

A DOUBLE ROW OF TYPE "S" SILT FENCE SHALL BE REQUIRED WHEN PLACED WITHIN 200' OF STATE WATERS AND AT THE TOE OF SLOPES GREATER THAN 10' IN HEIGHT.

GRADING NOTES:

COMPACTON:

COMPACTION OF THE BACKFILL OF ALL TRENCHES SHALL BE COMPACTED TO THE DENSITY OF 95% OF MODIFIED PROCTOR MAXIMUM DENSITY PER A.S.T.M. TEST D-698. BACKFILL MATERIAL SHALL BE FREE FROM ROOTS, STUMPS, OR OTHER FOREIGN DEBRIS, AND SHALL BE PLACED AT OR NEAR OPTIMUM MOISTURE. CORRECTION OF ANY TRENCH SETTLEMENT WITHIN A YEAR FROM THE DATE OF APPROVAL WILL BE THE RESPONSIBILITY OF THE CONTRACTOR.

BEDDING:

ALL STORM DRAIN AND SANITARY SEWER PIPES SHALL HAVE A CLASS "C" BEDDING AS A MINIMUM UNLESS NOTED OTHERWISE. EXCAVATE AND SHAPE BOTTOM OF TRENCH TO THE PROPER GRADE AND TO FIT THE LOWER PART OF THE PIPE EXTERIOR FOR A WIDTH OF A LEAST 50 PERCENT OF THE OUTSIDE DIAMETER OF THE PIPE. SIDES AND AREA OVER THE PIPE SHALL THEN BE FILLED WITH COMPACTED BACKFILL.

PAVING:

PAVING SHALL BE DONE IN ACCORDANCE WITH THE SPECIFICATIONS PROVIDED IN THESE STANDARDS. ALL PAVEMENT WITHIN THE GDOT R/W MUST CONFORM TO ALL GDOT PAVING STANDARDS.

CONCRETE:

3000 PSI COMPRESSIVE STRENGTH AT 28 DAYS, REINFORCING BARS SHALL CONFORM TO THE REQUIREMENTS OF ASTM A 615 GRADE 60.

FIELD CONDITIONS:

CONTRACTOR SHALL VERIFY FIELD CONDITIONS AFFECTING CONSTRUCTION, PARTICULARLY UTILITIES, PRIOR TO CONSTRUCTION. CHANGES IN CONSTRUCTION NECESSITATED BY FIELD CONDITIONS SHALL BE APPROVED BY THE OWNER OR OWNER'S ENGINEER PRIOR TO CONSTRUCTION. IN ACCORDANCE WITH STATE LAW, THE CONTRACTOR SHALL CALL 800-288-7411 AT LEAST THREE (3) WORKING DAYS PRIOR TO CONSTRUCTION FOR LOCATION OF UNDERGROUND UTILITIES.

CONSTRUCTION STAKING:

CONSTRUCTION STAKING IS THE RESPONSIBILITY OF THE CONTRACTOR.

CONSTRUCTION NOTES:

1. NO ADDITIONAL CONSTRUCTION OR IMPROVEMENTS, INCLUDING BUT NOT LIMITED TO WALLS, FENCES, SIGNS, SPRINKLER SYSTEMS, LIGHTS, TRESS, ETC., WILL BE ALLOWED ON THE ROAD RIGHT-OF-WAY.

2. THE CLAY COUNTY SHALL BE NOTIFIED 24 HOURS PRIOR TO ANY CONSTRUCTION.

3. ALL WATER MATERIALS AND WORKMANSHIP SHALL BE IN ACCORDANCE WITH THE CLAY COUNTY WATER & SEWER DEPARTMENT.

4. THE CONTRACTOR SHALL BE RESPONSIBLE FOR MAINTAINING A MARKED-UP SET OF DESIGN DRAWINGS SHOWING ALL "ASBUILT" CONDITIONS. THESE "RECORD DRAWINGS" SHALL BE MADE AVAILABLE TO THE DESIGNER AND/OR THE CITY INSPECTOR UPON REQUEST. THE MARK-UPS SHALL BE AT THE SITE AT ALL TIMES AND SHALL BE UTILIZED TO DEVELOP FINAL RECORD DRAWINGS.

5. ANY CHANGES IN THE HORIZONTAL ALIGNMENT SHOWN HEREON SHALL BE APPROVED BY THE DESIGN ENGINEER AND THE CLAY COUNTY PRIOR TO CONSTRUCTION.

6. THE CONTRACTOR IS RESPONSIBLE FOR ALL UTILITY LOCATIONS. CONTRACTOR SHOULD NOTIFY THE UTILITIES PROTECTION CENTER, INC. AT (800) 282-7411 THREE WORKING DAYS BEFORE CONSTRUCTION IS TO BEGIN.

7. THE CONTRACTOR IS RESPONSIBLE FOR THE INSTALLATION & MAINTENANCE OF ALL REQUIRED SEDIMENT CONTROL STRUCTURES.

8. ALL DISTURBED AREAS SHALL BE GRASSED IMMEDIATELY UPON COMPLETION OF BACK FILLING TRENCHES.

9. CLEARING LIMITS SHALL BE CLEARLY DELINEATED WITH TREE SAVE FENCE OR OTHER SUITABLE MEANS.

10. CONTRACTOR IS RESPONSIBLE FOR THE ADJUSTMENTS TO ALL EXISTING UTILITIES ON SITE TO FINAL GRADE.

NOTES:

DISPOSAL: STUMPS AND CONSTRUCTION DEBRIS SHALL BE DEPOSITED IN A PROPERLY PERMITTED LANDFILL.

PIPE: STORM DRAIN PIPES WILL BE CLASS III REINFORCED CONCRETE PIPE (RCP), TYPE II ALUMINIZED CORRUGATED STEEL PIPE (A2CSP) OR HDPE.

THE HORIZONTAL DATUM FOR THIS SURVEY IS STATE PLANE NORTH CAROLINA (NAD83).

ALL DISTANCES SHOWN ARE HORIZONTAL GROUND DISTANCES IN U.S. SURVEY FEET. (39.37 INCHES = 1 METER)

EROSION CONTROL NARRATIVE

PURPOSE OF DEVELOPMENT

THE PROPOSED PROJECT INVOLVES DREDGING 10,000 CUBIC YARDS OF MATERIAL FROM LAKE CHATUGE TO IMPROVE WATER DEPTH AND RECREATIONAL ACCESS. FOLLOWING THE DREDGING, A RETAINING WALL WILL BE CONSTRUCTED ALONG THE NEW SHORELINE, AND A BEACH AREA WILL BE DEVELOPED. THE PROJECT ALSO INCLUDES THE CONSTRUCTION OF A WALKING PATH AND GRADING OF THE SURROUNDING AREA TO ENHANCE USABILITY AND AESTHETICS.

SITE AND ADJACENT AREA CONDITIONS

THE PROJECT SITE IS CURRENTLY A GRASSY FIELD ADJACENT TO LAKE CHATUGE, WITH WETLANDS THAT DRAIN DIRECTLY INTO THE LAKE. THE SITE IS BORDERED BY HIGHWAY 175 AND IS ADJACENT TO SEVERAL SINGLE-FAMILY RESIDENTIAL PROPERTIES.

PROPOSED EROSION AND SEDIMENT CONTROL MEASURES

TO PREVENT SEDIMENT FROM ENTERING THE LAKE DURING CONSTRUCTION, A TURBIDITY CURTAIN WILL BE DEPLOYED WITHIN THE LAKE TO CONTAIN DISTURBED MATERIALS. A SILT FENCE WILL BE INSTALLED AROUND ALL DISTURBED AREAS TO INTERCEPT SEDIMENT RUNOFF. A STABILIZED CONSTRUCTION ENTRANCE WILL MINIMIZE OFF-SITE TRACKING OF SEDIMENT BY CONSTRUCTION VEHICLES. EXPOSED SOILS WILL BE STABILIZED PROMPTLY USING TEMPORARY SEEDING DURING CONSTRUCTION AND PERMANENT SEEDING UPON PROJECT COMPLETION TO ENSURE LONG-TERM EROSION CONTROL.

REVISION NUMBER	DATE	AFFECTED SHEETS	REVISION HISTORY CHART DESCRIPTION	P.E./ R.L.S. INITIAL

DATE	AGENCY	DEPARTMENT	SUBMITTAL HISTORY CHART DESCRIPTION	PERMIT TYPE	PERMIT NUMBER	APPROVAL DATE
01/08/25	TVA	PLANNING DIVISION	1st PLAN SUBMITTAL	LDP		

FOR:

STONE BRIDGE

GENERAL NOTES

LOCATED IN:

HAWASSEE TOWNSHIP
CLAY COUNTY, NORTH CAROLINA

ANY CHANGES OR ALTERATIONS MADE TO THIS DRAWING SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR. IT IS THE WRITTEN APPROVAL OF ROCHESTER & ASSOCIATES, INC. THAT THE SEAL SHOWN HEREON AND THE ORIGINAL DRAWINGS ARE KEPT ON FILE FOR VERIFICATION OF ANY CHANGES.

1ST SUBMITTAL

ROCHESTER

Engineering, Inc.

ROCHESTER ENGINEERING, INC.
425 OAK ST NW
GALESVILLE, GA 30501
770.718.0600 | rochester.dccm.com

ANY CHANGES OR ALTERATIONS MADE TO THIS DRAWING SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR. IT IS THE WRITTEN APPROVAL OF ROCHESTER & ASSOCIATES, INC. THAT THE SEAL SHOWN HEREON AND THE ORIGINAL DRAWINGS ARE KEPT ON FILE FOR VERIFICATION OF ANY CHANGES.

1ST SUBMITTAL

SHEET

2

OF

6

DATE: 01/08/25



SCALE: N.T.S.

DRAWN BY: CMA

CHECKED BY: CMA

DESIGNED BY: CMA


IN CHARGE: CMA



EXISTING SITE PLAN
FOR:
STONE BRIDGE

LOCATED IN:
HAMASSEE TOWNSHIP
CLAY COUNTY, NORTH CAROLINA

ANY CHANGES OR ALTERATIONS MADE TO THIS DRAWING SHALL BE THE RESPONSIBILITY OF THE CLIENT. THE WRITTEN APPROVAL OF ROCHESTER ENGINEERING, INC. IS REQUIRED FOR ANY CHANGES TO BE MADE TO THIS DRAWING. ORIGINAL DRAWINGS ARE KEPT ON FILE FOR VERIFICATION OF ANY CHANGES.




1ST SUBMITTAL

SHEET	3
OF	6

DATE: 07/08/25
SCALE: 1" = 60'
JOB NO.: 2505 TMM
DRAWN BY: CSM
CHECKED BY: CSM
APPROVED BY: CSM


DATE:		PAGE:																				
	<div data-bbox="1056 320 1518 546"> <p style="text-align: center;">SPACING GUIDE FOR SLOPE BREAKS</p> <table border="1"> <thead> <tr> <th></th><th>SLOPE</th><th>SPACING (FT)</th></tr> </thead> <tbody> <tr> <td rowspan="3">Steep Slopes</td><td>2:1</td><td>20</td></tr> <tr> <td>3:1</td><td>35</td></tr> <tr> <td>4:1</td><td>45</td></tr> <tr> <td rowspan="5">Long Slopes</td><td>15-25%</td><td>50</td></tr> <tr> <td>10-15%</td><td>80</td></tr> <tr> <td>6-10%</td><td>125</td></tr> <tr> <td>3-6%</td><td>200</td></tr> <tr> <td><3%</td><td>300</td></tr> </tbody> </table> </div> <div data-bbox="1048 555 1528 582"> <p>Use slope breaks, such as diversions, wattles, or benches, as appropriate, to reduce the length of cut-and-fill slope to limit sheet and rill erosion and prevent gullying.</p> </div> <div data-bbox="1064 598 1165 610"> <p>MAINTENANCE:</p> </div> <div data-bbox="1075 613 1469 750"> <ol style="list-style-type: none"> Periodically check all graded areas and the supporting erosion and sedimentation control practices, especially after heavy rainfalls. Promptly remove all sediment from diversions and other water-disposal practices. If washouts or breaks occur, repair immediately. Prompt maintenance of small eroded areas before they become significant gullies is an essential part of an effective erosion and sedimentation control plan. </div> <div data-bbox="1535 283 1584 296"> <p>NOTES:</p> </div> <div data-bbox="1543 302 1943 775"> <ol style="list-style-type: none"> Construct and maintain all erosion and sediment control practices and measures in accordance with the approved sedimentation control plan and construction schedule. Remove good topsoil from areas to be graded and filled, and preserve it for use in finishing the grading of all critical areas. Scarify areas to be topsoiled to a minimum depth of 2 inches before placing topsoil. Clear and grub areas to be filled by removing trees, vegetation, roots, or other objectionable material that would affect the planned stability of the fill. Ensure that fill material is free of brush, rubbish, rocks, logs, stumps, building debris, and other materials inappropriate for constructing stable fills. Place all fill in layers not to exceed 9 inches in thickness, and compact the layers as required to reduce erosion, slippage, settlement, or other related problems. Do not incorporate frozen, soft, mucky, or highly compressible materials into a frozen foundation, due to possible subsidence and slippage. Do not place fill on a frozen foundation, due to possible subsidence and slippage. Keep diversions and other water conveyance measures free of sediment during all phases of development. Handle seeps or springs encountered during construction in accordance with approved methods (subsurface drain). Permanently stabilize all graded areas immediately after final grading is completed on each area in the grading plan. Apply temporary stabilization measures on all graded areas when work is to be interrupted or delayed for 30 days or longer. Show topsoil, stockpiles, borrow areas, and spoil areas on the plans, and make sure they are adequately protected from erosion. Include final stabilization of these areas in the plan. </div> <div data-bbox="1030 805 1124 839"> </div> <div data-bbox="1396 811 1580 833"> <h1>LAND GRADING</h1> </div> <div data-bbox="1843 805 1966 839"> <p>Effective Date: 9/1/2023 in accordance with the 2013 Design Manual Updates</p> </div>		SLOPE	SPACING (FT)	Steep Slopes	2:1	20	3:1	35	4:1	45	Long Slopes	15-25%	50	10-15%	80	6-10%	125	3-6%	200	<3%	300
	SLOPE	SPACING (FT)																				
Steep Slopes	2:1	20																				
	3:1	35																				
	4:1	45																				
Long Slopes	15-25%	50																				
	10-15%	80																				
	6-10%	125																				
	3-6%	200																				
	<3%	300																				

DATE: _____	PAGE: _____																													
NON-INVASIVE PERMANENT SEEDING RECOMMENDATIONS FOR LATE WINTER AND EARLY SPRING	NON-INVASIVE PERMANENT SEEDING RECOMMENDATIONS FOR SUMMER	NON-INVASIVE PERMANENT SEEDING RECOMMENDATIONS FOR FALL																												
SEEDING MIXTURE <table border="1"> <thead> <tr> <th>Species</th><th>Rate</th></tr> </thead> <tbody> <tr> <td>Centipede</td><td>5 lbs/acre</td></tr> <tr> <td>Indian Woodoats</td><td>1.5-2.5 lbs/acre*</td></tr> <tr> <td>Virginia Wild Ryegrass</td><td>4-6 lbs/acre</td></tr> </tbody> </table> <p>*Depending upon mix with other species. See table 6.11.d from Chapter 6 of the NC Erosion and Sediment Control Planning and Design Manual.</p>	Species	Rate	Centipede	5 lbs/acre	Indian Woodoats	1.5-2.5 lbs/acre*	Virginia Wild Ryegrass	4-6 lbs/acre	SEEDING MIXTURE <table border="1"> <thead> <tr> <th>Species</th><th>Rate</th></tr> </thead> <tbody> <tr> <td>Indian Woodoats</td><td>1.5-2.5 lbs/acre*</td></tr> <tr> <td>Virginia Wild Ryegrass</td><td>4-6 lbs/acre*</td></tr> </tbody> </table> <p>*Depending upon mix with other species. See table 6.11.d from Chapter 6 of the NC Erosion and Sediment Control Planning and Design Manual.</p>	Species	Rate	Indian Woodoats	1.5-2.5 lbs/acre*	Virginia Wild Ryegrass	4-6 lbs/acre*	SEEDING MIXTURE <table border="1"> <thead> <tr> <th>Species</th><th>Rate</th></tr> </thead> <tbody> <tr> <td>Hard Fescue</td><td>15 lbs/acre</td></tr> <tr> <td>Switchgrass</td><td>2.5-3.5 lbs/acre*</td></tr> <tr> <td>Indian Grass</td><td>5-7 lbs/acre*</td></tr> <tr> <td>Big Bluestem</td><td>5-7 lbs/acre*</td></tr> <tr> <td>Indian Woodoats</td><td>1.5-2.5 lbs/acre*</td></tr> <tr> <td>Virginia Wild Ryegrass</td><td>4-6 lbs/acre*</td></tr> </tbody> </table> <p>*Depending upon mix with other species. See table 6.11.d from Chapter 6 of the NC Erosion and Sediment Control Planning and Design Manual.</p>	Species	Rate	Hard Fescue	15 lbs/acre	Switchgrass	2.5-3.5 lbs/acre*	Indian Grass	5-7 lbs/acre*	Big Bluestem	5-7 lbs/acre*	Indian Woodoats	1.5-2.5 lbs/acre*	Virginia Wild Ryegrass	4-6 lbs/acre*
Species	Rate																													
Centipede	5 lbs/acre																													
Indian Woodoats	1.5-2.5 lbs/acre*																													
Virginia Wild Ryegrass	4-6 lbs/acre																													
Species	Rate																													
Indian Woodoats	1.5-2.5 lbs/acre*																													
Virginia Wild Ryegrass	4-6 lbs/acre*																													
Species	Rate																													
Hard Fescue	15 lbs/acre																													
Switchgrass	2.5-3.5 lbs/acre*																													
Indian Grass	5-7 lbs/acre*																													
Big Bluestem	5-7 lbs/acre*																													
Indian Woodoats	1.5-2.5 lbs/acre*																													
Virginia Wild Ryegrass	4-6 lbs/acre*																													
Seeding Dates Coastal or Eastern Piedmont for Centipede- Sept. 1 - May 1 Coastal and Piedmont for Indian Woodoats and Virginia Wild Ryegrass- Feb 15 - April 1 Mountains for Indian Woodoats and Virginia Wild Ryegrass- March 1 - May 15	Seeding Dates Mountains - July 15- Aug 15 Piedmont - Aug 15 - Oct 15	Seeding Dates Mountains - Hard Fescue- Aug 1 - June 1 Mountains- Switchgrass, Indian Grass, Big Bluestem- Dec 1 - April 15 Piedmont and Coastal- Switchgrass, Indian Grass, Big Bluestem- Dec 1 - April 1 Coastal- Indian Woodoats and Virginia Wild Ryegrass- Sept 1 - Nov 1																												
Maintenance: Significant maintenance may be required to obtain desired cover.	Maintenance: Indian Woodoats and Virginia Wild Ryegrass are both sun and shade tolerant.	Maintenance: Fescue is not recommended for slopes > 5%. Prefers shade.																												
SEED BED PREPARATION:																														
LIMING: Apply lime according to soil test recommendations. If the pH (acidity) of the soil is not known, an application of ground agricultural limestone at the rate of 1 to 1½ tons/acre on coarse/textured soils and 2-3 tons/acre on fine-textured soils is usually sufficient. Apply limestone uniformly and incorporate into the top 4-6 inches of soil. Soils with a pH of 6 or higher need not be limed. FERTILIZER: Soil test results are used to determine if and when fertilizers are needed. If fertilizers are needed, apply a 10-10-10 liquid fertilizer at 700-1,000 lbs/acre. Both fertilizer and lime should be incorporated into the top 4-6 inches of soil. If a hydraulic seeder is used, do not mix seed and fertilizer more than 30 minutes before application. SURFACE ROUGHENING: If recent tillage operations have resulted in a loose surface additional roughening may not be required, except to break up large clods. If rainfall causes the surface to become sealed or crusted, loosen it just prior to seeding by tilling, harrowing, or other suitable methods for fine grading. The finished grade should be a smooth even soil surface with a loosen uniformly fine texture. All ridges and depressions shall be removed and filled to provide the approved surface drainage. Planting is to be done immediately after finished grades are obtained and seedbed preparation is completed.																														
NOTES:																														
1. Permanent seeding, sodding or other means of stabilization are required when all construction work is completed according to the NPDES stormwater table. 2. Seeding, sodding or other means of stabilization are required for all areas to be seeded, sodded or planted. 3. Use a seeding mix that will produce fast-growing nurse crops and includes non-invasive species that will eventually provide a permanent groundcover. Soil blankets may be used in lieu of nurse crops. 4. Mat, tack or crimp mulch, as needed to stabilize seeded areas until root establishment. Mulch must cover at least 80% of the soil surface. 5. Ground cover should be maintained until permanent vegetation is established and stable against accelerated erosion.																														



PERMANENT SEEDING

Effective Date: 9/1/2023
in accordance with the 2013
Design Manual Updates




TEMPORARY GRAVEL CONSTRUCTION ENTRANCE/EXIT

Effective Date: 9/1/2023
In accordance with the 2013
Design Manual Updates

DATE:

PAGE:



Public Road

6\" MIN.

2-3\" COURSE AGGREGATE

AS REQUIRED 42\" MIN.

IF 50' CANNOT BE REACHED, A LENGTH SUFFICIENT ENOUGH TO RETAIN SEDIMENT ON SITE AND OFF ROADWAYS.

50' MIN.


GEOTEXTILE FABRIC TO BE USED IN LOCATIONS SUBJECT TO SEEPAGE OR HIGH WATER TABLE.

Construction:

1. Clear the entrance and exit area of all vegetation, roots, and other objectionable material and properly grade it.
2. Place the gravel to the specific grade and dimensions shown on the plans, and smooth it.
3. Provide drainage to carry water to a sediment trap or other suitable outlet.
4. Use geotextile fabrics in order to improve stability of the foundation in locations subject to seepage or high water table.

Maintenance:

1. Inspect all measures at least weekly and after each rainfall of 1.0 inch or greater. Make any required repairs immediately.
2. Maintain the gravel pad in a condition to prevent mud or sediment from leaving the construction site. This may require periodic tamping with 2-inch stone.
3. Sediment on roadways is to be removed immediately by broom and shovel, either by manual or mechanical means, and not to be washed off where it has the potential to enter a stream, drainage way or storm drain system.



TEMPORARY GRAVEL CONSTRUCTION ENTRANCE/EXIT

Effective Date: 9/1/2023
In accordance with the 2013
Design Manual Updates

DATE: _____ **PAGE:** _____

8' MAX. STANDARD STRENGTH FABRIC WITH WIRE FENCE
6' MAX. EXTRA STRENGTH FABRIC WITHOUT WIRE FENCE

STEEL POST
PLASTIC OR WIRE TIES
WIRE FENCE
18-24"
8' DOWN & 4' FORWARD ALONG THE TRENCH
24"
FILTER FABRIC

WIRE FENCE
PLASTIC OR WIRE
STEEL POST
24"
4" MIN.
CROSS SECTION VIEW
BACKFILL TRENCH AND COMPACT THOROUGHLY
8' MIN.
UPSLOPE

Notes:

- Construct the sediment barrier of standard strength or extra strength synthetic filter fabrics.
- Ensure that the height of the sediment fence does not exceed 24 inches above the ground. (Higher fences may impound volumes of water sufficient to cause failure of the structure)
- Construct the filter fabric from a continuous roll cut to the length of the barrier to avoid joints. When joints are necessary, securely fasten the filter cloth only at a support post with 4 feet minimum overlap to the next post.
- Support standard strength filter fabric by wire mesh fastened securely to the upslope side of the posts. Extend the wire mesh support to the bottom of the trench. Fasten the wire reinforcement, then fabric on the upslope side of the fence post. Wire or plastic zip ties should have a minimum 50 pound tensile strength.
- When a wire mesh support fence is used, space posts a maximum of 8 feet apart. Supports should be driven securely into the ground a minimum of 24 inches. Wire mesh should be a minimum 14-gauge with 6 inch mesh strength.
- Extra strength filter fabric with 6 foot post spacing does not require a wire mesh support fence. Securely fasten the filter fabric directly to posts. Wire or plastic zip ties should have a minimum of 50 pound tensile strength.
- Excavate the trench approximately 4 inches wide and 8 inches deep along the proposed line of the posts and upslope from the barrier.
- Place 12 inches of fabric along the bottom and side of the trench.
- Backfill the trench with soil placed over the filter fabric and compact. Thorough compaction of the backfill is critical to silt fence performance.
- Do not attach filter fabric to existing trees.
- Do not place across ditches, streams, or any other areas of concentrated flow.

Max. Slope Length and Slope for Which Sediment Fence is Applicable

Slope	Slope Length (ft)	Max. Area (ft ²)
<2%	100	10,000
2 to 5%	75	7,500
5 to 10%	50	5,000
10 to 20%	25	2,500
>20%	15	1,500

Maintenance:

- Inspect all measures at least weekly and after each rainfall of 1.0 inch or greater. Make any required repairs immediately.
- Should the fabric of a sediment fence collapse, tear, decompose, or become ineffective, replace it promptly.
- Remove sediment deposits as necessary to provide adequate storage volume for the next rain and reduce pressure on the fence. Take care to avoid undermining the fence during cleanouts.
- Remove all fencing materials and unstable sediment deposits and bring the area to grade and stabilize it after the contributing drainage area has been properly stabilized.

[illegible]

Rochester
Engineering, Inc.

Rochester Engineering, INC.
425 Oak St NW, Gainesville, GA 30501
770.718.0600 | rochester.dccm.com

Implementing the details and specifications on this plan sheet will result in the construction activity being considered compliant with the Ground Stabilization and Materials Handling sections of the NCG01 Construction General Permit (Sections E and F, respectively). The permittee shall comply with the Erosion and Sediment Control plan approved by the delegated authority having jurisdiction. All details and specifications shown on this sheet may not apply depending on site conditions and the delegated authority having jurisdiction.

Required Ground Stabilization Timeframes		
Site Area Description	Stabilize within this many calendar days after ceasing land disturbance	Timeframe variations
(a) Perimeter dikes, swales, ditches, and perimeter slopes	7	None
(b) High Quality Water (HQP) Zones	7	None
(c) Slopes steeper than 3:1	7	If slopes are 10' or less in length and are not steeper than 2:1, 14 days are allowed
(d) Slopes 3:1 to 4:1	14	- 7 days for slopes greater than 50' in length and with slopes steeper than 4:1 - 7 days for perimeter dikes, swales, ditches, perimeter slopes and HQW Zones - 10 days for Falls Lake Watershed
(e) Areas with slopes flatter than 4:1	14	- 7 days for perimeter dikes, swales, ditches, perimeter slopes and HQW Zones - 10 days for Falls Lake Watershed unless there is zero slope

Temporary Stabilization	Permanent Stabilization
<ul style="list-style-type: none"> Temporary grass seed covered with straw or other mulches and tackifiers Hydroseeding Rollled erosion control products with or without temporary grass seed Appropriately applied straw or other mulch Plastic sheeting 	<ul style="list-style-type: none"> Permanent grass seed covered with straw or other mulches and tackifiers Geotextile fabrics such as permanent soil reinforcement matting Hydroseeding Straw or other permanent plantings covered with mulch Uniform and evenly distributed ground cover sufficient to restrain erosion Structural methods such as concrete, asphalt or retaining walls Rollled erosion control products with grass seed

1. Select flocculants that are appropriate for the soils being exposed during construction, selecting from the *NC DWR List of Approved PAMS/Flocculants*.
2. Apply flocculants at or before the inlets to Erosion and Sediment Control Measures.
3. Apply flocculants at the concentrations specified in the *NC DWR List of Approved PAMS/Flocculants* and in accordance with the manufacturer's instructions.
4. Provide ponding area for containment of treated Stormwater before discharging offsite.
5. Store flocculants in leak-proof containers that are kept under storm-resistant cover or surrounded by secondary containment structures.

1. Maintain vehicles and equipment to prevent discharge of fluids.
2. Provide drip pans under any stored equipment.
3. Identify leaks and repair as soon as feasible, or remove leaking equipment from the project.
4. Collect all spent fluids, store in separate containers and properly dispose as hazardous waste (recycle when possible).
5. Remove leaking vehicles and construction equipment from service until the problem has been corrected.
6. Bring used fuel, lubricants, coolants, hydraulic fluids and other petroleum products to a recycling or disposal center that handles these materials.

1. Never bury or burn waste. Place litter and debris in approved waste containers.
2. Provide a sufficient number and size of waste containers (e.g. dumpster, trash receptacle) on site to contain construction and domestic wastes.
3. Locate waste containers at least 50 feet away from storm drain inlets and surface waters unless other alternatives are clearly more reasonable.
4. Locate waste containers on areas that do not receive substantial amounts of runoff from upland areas and does not drain directly to a storm drain, stream or wetland.
5. Cover waste containers at the end of each workday and before storm events or cover secondary containment. Repair or replace damaged waste containers.
6. Do not allow lightweight items to waste containers during times of high winds.
7. Empty waste containers as needed to prevent overflow. Clean up immediately if containers overflow.
8. Dispose waste off-site at an approved disposal facility.
9. On business days, clean up and dispose of waste in designated waste containers.

1. Do not dump paint and other liquid waste into storm drains, streams or wetlands.
2. Locate paint washouts at least 50 feet away from storm drain inlets and surface waters unless no other alternatives are reasonably available.
3. Contain liquid wastes in a controlled area.
4. Containment must be labeled, sized and placed appropriately for the needs of site.
5. Prevent the discharge of soaps, solvents, detergents and other liquid wastes from construction sites.

1. Install portable toilets on level ground, at least 50 feet away from storm drains, streams or wetlands unless there is no alternative reasonably available. If 50 foot offset is not attainable, provide relocation of portable toilet behind silt fence or place on a gravel pad and surround with sand bags.
2. Provide staking or anchoring of portable toilets during periods of high winds or in high foot traffic areas.
3. Monitor portable toilets for leaking and properly dispose of any leaked material. Utilize a licensed sanitary waste hauler to remove leaking portable toilets and replace with properly operating unit.

1. Show stockpile locations on plans. Locate earthen-material stockpile areas at least 50 feet away from storm drain inlets, sediment basins, perimeter sediment controls and surface waters unless it can be shown no other alternatives are reasonably available.
2. Protect stockpiles with silt fence installed along toe of slope with a minimum offset of five feet from the toe of stockpile.
3. Provide stable stone access point when feasible.
4. Stabilize stockpile within the timeframes provided on this sheet and in accordance with the approved plan and any additional requirements. Soil stabilization is defined as vegetative, physical or chemical coverage techniques that will restrain accelerated erosion on disturbed soils for temporary or permanent control needs.

1. Do not discharge concrete or cement slurry from the site.
2. Dispose of, or recycle/seal, hardened concrete residue in accordance with local and state solid waste regulations and at an approved facility.
3. Manage washout from mortar mixers in accordance with the above item and in addition place the mortar and associated materials on impervious barrier and with lot perimeter soil fence.
4. Install temporary concrete washouts per local requirements, where applicable. If an alternate method or product is to be used, contact your approval authority for review and approval. If approved, the contractor shall use one of the two types of temporary concrete washouts provided on this document.
5. Do not use concrete washouts for dewatering or storing defective curb or sidewalk sections. Stormwater accumulated within the washout may not be pumped into or discharged to the storm drain system or receiving surface waters. Liquid waste must be pumped out and removed from the project.
6. Locate washouts at least 50 feet from storm drain inlets and surface waters unless it can be shown that no other alternatives are reasonably available. At a minimum, install protection of storm drain inlet(s) closest to the washout which could receive spillage or overflow.
7. Locate washouts in an easily accessible area, on level ground and install a stone entrance pad in front of the washout. Additional controls may be required by the approving authority.
8. Install at least one sign directing concrete trucks to the washout within the project limits. Post signage at the washout itself to identify the location.
9. Remove leavings from the washout when at approximately 75% capacity to limit overflow events. Replace the tarp, sand bags or other temporary structural components when no longer functional. When utilizing alternative or proprietary products, follow manufacturer's instructions.
10. After completion of the project, remove the washout and any remaining leavings and dispose of in an approved disposal facility. Fill pit, if applicable, and stabilize any erosion caused by removal of washout.

1. Store and apply herbicides, pesticides and rodenticides in accordance with label restrictions.
2. Store herbicides, pesticides and rodenticides in their original containers with the label, which lists directions for use, ingredients and first aid steps in case of accidental poisoning.
3. Do not store herbicides, pesticides and rodenticides in areas where flooding is possible or where they may spill or leak into wells, stormwater drains, ground water or surface water. If a spill occurs, clean area immediately.
4. Do not stockpile these materials onsite.

1. Create designated hazardous waste collection areas on-site.
2. Place hazardous waste containers under cover or in secondary containment.
3. Do not store hazardous chemicals, drums or bagged materials directly on the ground.

EFFECTIVE: 04/01/19

SECTION A: SELF-INSPECTION

Self-inspections are required during normal business hours in accordance with the table below. When adverse weather or site conditions would cause the safety of the inspection personnel to be in jeopardy, the inspection may be delayed until the next business day on which it is safe to perform the inspection. In addition, when a storm event of equal to or greater than 1.0 inch occurs outside of normal business hours, the self-inspection shall be performed upon the commencement of the next business day. Any time when inspections were delayed shall be noted in the Inspection Record.

NOTE: The rain inspection resets the required 7 calendar day inspection requirement.

Sediment basins and traps that receive runoff from drainage areas of one acre or more shall use outlet structures that withdraw water from the surface when these devices need to be drawn down for maintenance or close out unless this is infeasible. The circumstances in which it is not feasible to withdraw water from the surface shall be rare (for example, times with extended cold weather). Non-surface withdrawals from sediment basins shall be allowed only when all of the following criteria have been met:

- (a) The E&S plan authority has been provided with documentation of the non-surface withdrawal and the specific time periods or conditions in which it will occur. The non-surface withdrawal shall not commence until the E&S plan authority has approved these items,
- (b) The non-surface withdrawal has been reported as an anticipated bypass in accordance with Part III, Section C, Item 2)(c) and (d) of this permit,
- (c) Dewatering discharges are treated with controls to minimize discharges of pollutants from stormwater that is removed from the sediment basin. Examples of appropriate controls include properly sited, designed and maintained dewatering tanks, wet tanks, and filtration systems,
- (d) Vegetated, upland areas of the sites or a properly designed stone pad is used to the extent feasible at the outlet of the dewatering treatment devices described in Item (c) above,
- (e) Velocity dissipation devices such as check dams, sediment traps, and riprap are provided at the discharge points of all dewatering devices, and
- (f) Sediment removed from the dewatering treatment devices described in Item (c) above is disposed of in a manner that does not cause deposition of sediment into waters of the United States.

The approved E&SC plan as well as any approved deviation shall be kept on the site. The approved E&SC plan must be kept up-to-date throughout the coverage under this permit. The following items pertaining to the E&SC plan shall be kept on site and available for inspection at all times during normal business hours.

2. Additional Documentation to be Kept on Site
In addition to the E&SC plan documents above, the following items shall be kept on the site and available for inspectors at all times during normal business hours, unless the Division provides a site-specific exemption based on unique site conditions that make this requirement not practical:

- (a) This General Permit as well as the Certificate of Coverage, after it is received.
- (b) Records of inspections made during the previous twelve months. The permittee shall record the required observations on the Inspection Record Form provided by the Division on similar inspection form that includes all the required elements. Use of electronically-able observations in lieu of the required paper copies will be allowed if shown to provide equal access and utility as the hard-copy records.

3. Documentation to be Retained for Three Years
All data used to complete the e-NOI and all inspection records shall be maintained for a period of three years after project completion and made available upon request. [40 CFR 122.41]

NS FOR MAINTENANCE OR CLOSE OUT

1. Occurrences that Must be Reported

Permittees shall report the following occurrences:

(a) Visible sediment deposition in a stream or wetland.

- (b) Oil spills if:
 - They are 25 gallons or more,
 - They are less than 25 gallons but cannot be cleaned up within 24 hours,
 - They cause sheen on surface waters (regardless of volume), or
 - They are within 100 feet of surface waters (regardless of volume).
- (c) Releases of hazardous substances in excess of reportable quantities under Section 102 of the Clean Water Act (Ref. 40 CFR 110.3 and 40 CFR 117.3) or Section 102 of CERCLA (Ref. 40 CFR 302.4) or G.S. 143-215.85.
- (d) Anticipated bypasses and unanticipated bypasses.
- (e) Noncompliance with the conditions of this permit that may endanger health or the environment.

After a permittee becomes aware of an occurrence that must be reported, he shall contact the appropriate Division regional office within the timeframes and in accordance with the other requirements listed below. Occurrences outside normal business hours may also be reported to the Department's Environmental Emergency Center personnel at (800) 858-0368.

Occurrence	Reporting Timeframes (After Discovery) And Other Requirements
(a) Visible sediment deposition in a stream or wetland	<p>Within 24 hours, an oral or electronic notification.</p> <p>Within 7 calendar days, a report that contains a description of the sediment and actions taken to address the cause of the deposition.</p> <p>Division staff may waive the requirement for a written report on a case-by-case basis.</p> <p>If the stream is named on the DC 303.4(a)(1)(g) as impaired for sediment-related causes, the permittee may be required to perform additional monitoring, inspections or apply more stringent practices if staff determine that additional monitoring or inspections are needed to assure compliance with the federal or state impaired-waters conditions.</p>
(b) Oil spills and release of hazardous substances per item 1(b) (d) above	<p>Within 24 hours, an oral or electronic notification. The notification shall include information about the date, time, nature, volume and location of the spill or release.</p>
(c) Anticipated bypasses [40 CFR 122.412.(m)(3)]	<p>A report at least ten days before the date of the bypass, if possible.</p> <p>The report shall include an evaluation of the anticipated quality and effect of the bypass.</p>
(d) Unanticipated bypasses [40 CFR 122.412.(m)(3)]	<p>Within 24 hours, an oral or electronic notification.</p> <p>Within 7 calendar days, a report that includes an evaluation of the quality and effect of the bypass.</p>
(e) Noncompliance with the conditions of this permit that may endanger human health, the anticipated or actual environment [40 CFR 122.412.(f)(7)]	<p>Within 24 hours, an oral or electronic notification.</p> <p>Within 7 calendar days, a report that contains a description of the noncompliance, and its causes; the period of noncompliance, including exact dates and times; and if the noncompliance has not been corrected, the anticipated or actual consequences expected to continue; and steps taken or planned to reduce, eliminate, and prevent recurrence of the noncompliance. [40 CFR 122.412.(f)(6).</p> <p>Division staff may waive the requirement for a written report on a case-by-case basis.</p>

EFFECTIVE: 04/01/19